North York District
5100 Yonge Street
Toronto, ON M2N 5V7
Tel: 4163975330
Fax:4163957589

BUILDING PERMIT

This card must be kept posted in a conspicuous place on site of construction.

25 256572 BLD 00 SR

Site Address 173 WOBURN AVE

Project Description Laneway / Rear Yard Suite;

New Laneway / Rear Yard Suite

Date Issued Friday July 10, 2026

Kamal Gogna, P. Eng.
Chief Building Official &
Executive Director

Tony D'Amico
Deputy Chief Building Official and
Director

TORONTO Building North York District

THIS IS YOUR PERMIT TO CONSTRUCT
PERMIT NUMBER: 25 256572 BLD 00 SR

Owner:	**Address:**
SANDRA SACCONE	103 GLEN LONG AVE TORONTO, ON M6B 2M4 CAN
NCOLA SACCONE	173 WOBURN AVE TORONTO, ON M5M 1K8 CAN

Project Description: Laneway / Rear Yard Suite; New Laneway / Rear Yard Suite

Project Location: 173 WOBURN AVE

Ward:

The issuance of this permit is based on the drawings, specifications, details and information submitted with the application. The submitted documents have been reviewed for compliance with the Ontario Building Code, Zoning By-laws, applicable regulations and legislation.

The referenced permit number listed above and on your permit placard also appears on all plans reviewed for this building permit application. The validity of this permit is restricted to the person/company named as owner. Permit ownership cannot be transferred unless prior written authorization is given by the Chief Building Official.

The extent of construction authorized under this permit is limited to the description contained herein as follows:
Proposal to construct a 2 storey laneway suite with a ground floor garage.
See also 24 227434 ZAP and 25 198719 MV.

Stated work and use must be in accordance with the plans, specifications, building permit notes and other information issued with this building permit. Changes to any documents submitted are not to be made unless prior authorization is obtained from the Chief Building Official or designate. False information may be grounds for revocation of the building permit.

Notwithstanding, it is the responsibility of the owner to comply with requirements of the Ontario Building Code and applicable laws as well as to ensure compliance ..

The permit placard must be posted in a conspicuous place on the construction site.

Tony D'Amico
Deputy Chief Building Official
North York District

Issued by: Toronto Building Issuance Team

Date Issued: July 10, 2026

Toronto Building North York District

Please see the second page of this letter for additional requirements and inspection information.

TORONTO Building North York District

WHEN YOU BEGIN DEMOLITION/CONSTRUCTION ...

Site Fencing

As soon as construction or demolition starts, your site must be entirely surrounded by a fence which is in compliance with the City of Toronto Municipal Code Chapter 363, Article III. The minimum requirement is plastic mesh fencing, 1.2 metres high, tied to posts spaced no more than 1.2 metres apart with an 11 gauge top and bottom wire threaded through the mesh and looped around each post. The Municipal Code is available on the City website at:

http://www.toronto.ca/legdocs/municode/1184_363.pdf

Construction Noise

Any construction which generates noise is prohibited in residential areas between the hours of 7:00 p.m. one day to 7:00 a.m. the next day, 9:00 a.m. on Saturdays, and all day Sunday and Statutory holidays.

When To Call For Inspection

You are required by Division C, Part 1, Article 1.3.5.1. of the Ontario Building Code, to notify the building inspection office at several prescribed stages of construction. Please contact the building inspection office at the telephone number listed below, when each of the following stages are substantially complete:

Inspection Stages

* Excavation/Shoring	* Footings/Foundations	* Structural Framing
* Insulation/Vapour Barrier	* Fire Separations	* Fire Protection Systems
* Fire Access Routes	* Interior Final Inspection	* Exterior Final Inspection
* Site Grading Inspection	* Pool Suction/Gravity Outlets	* Pool Circulation System
* Sewers/Drains/Sewage System	* Water Service	* Fire Service
* Drain/Waste/Vents	* Water Distribution	* Plumbing Final
* HVAC/Extraction Rough-in	* HVAC Final	* Occupancy
* Demolition	* Repair/Retrofit	* System
* Change of Use	* Security Device	* Tent/Portable Classroom

To Schedule your Next Mandatory Inspection

When you are ready to book your inspection, you may request an inspection online from your computer or smart phone using Toronto Building's Inspection Request web application at www.toronto.ca/building-inspection-request.

Alternatively, you may contact your local building inspection office by telephone at 416-338-0700, by fax 416-696-4179 or by email to NYBldgInsp@toronto.ca.

Inspections will take place within two days commencing at the start of business on the day following your notification (Inspection Request).

Please leave a telephone number where you can be reached or a message can be left.

The inspector assigned to your project is Kyle Purcell (416) 395-7569

Residential Infill Construction ***Good Neighbour Guide***

To improve communication with residents, the Toronto Building Division has developed a **Residential Infill website** that provides easy-to-follow resources, such as the ***Good Neighbour Guide for Residential Infill Construction.***

This guide is intended for property owners, builders, and contractors starting a construction project in an established neighbourhood, and for neighbours in the area. It outlines requirements, best practices, and communication tips

For more information, and to download a copy of the guide, visit: *www.toronto.ca/infill*

PERMIT PLANS MUST BE ON SITE

Your permit plans and specifications must be on site at all times. Inspections are conducted with your copy of the plans.

TORONTO Building

Kamal Gogna, P. Eng.
Chief Building Official & Executive Director

July 10, 2026

Toronto Building
Toronto City Hall
12th Floor, East Tower
100 Queen Street West
Toronto, Ontario, M5H 2N2

BULLETIN - CONSTRUCTION SAFETY

The responsibilities of the City of Toronto under the Occupational Health and Safety Act apply to all our employees regardless of the location at which they are working.

Responsibilities for the Construction Safety Regulations on construction sites are clearly spelled out in the Act under the definitions of constructor, employer, supervisor and worker.

The City of Toronto believes that the goal of safe and injury free construction sites is a priority for all parties involved in building construction.

Safety training for the City of Toronto Building Inspectors is mandatory. However the delivery of a safe working environment on construction sites must include the compliance of individual builders with the Occupational Health and Safety Act.

Safety measures include the following:
1. Temporary guards on all openings,
2. Correct use of ladders,
3. Temporary or permanent stairs above or below grade by the time the sub floor is complete,
4. Clear and safe access to the site,
5. Protection of trenches and excavation below four feet deep, and
6. Correct use of fall prevention equipment where required.

As the employer responsible for the safety of building inspectors, the City of Toronto has instructed its Building Inspectors not to conduct inspections on sites where conditions exist that could jeopardize their health and safety.

The following are examples of conditions which may jeopardize the health and safety of inspectors:
1. Guards are missing,
2. Ladders do not meet regulations,
3. Temporary or permanent stairs, above or below grade, to all floor levels are not provided as required.
4. Access to the site has impediments or hazards, or
5. Trenches or excavations lack required shoring or slope of bank.

Prior to calling for an inspection the appropriate safety measures shall be in place as a site inadequately provided with these measures is not ready for inspection. The City of Toronto Building Inspectors will cooperate with builders regarding the timing of making provision for these safety measures. However, if the measures are not provided, an Order Not To Cover could be issued and the Ministry of Labour informed.

We look forward to working with you toward the goal of a safe environment for all workers.

Notice of Project - Please be advised that the Ministry of Labour requires a Notice of Project be filed with them before starting any project costing $50,000 or more.

For more information about the Notice of Project form and construction information please visit Ministry of Labour website at: **https://www.labour.gov.on.ca/english/hs/forms/**

Report an Incident
Notify the ministry of fatalities, critical injuries, work refusals, reprisals and unsafe work practices.
Ministry of Labour Health _Safety Contact Centre

Toll-free: 1-877-202-0008
TTY: 1-855-653-9260
Fax: 905-577-1316

Construction of the work approved in this building permit must be carried out with reasonable care to ensure protection for everyone on the construction site from the hazards associated with all overhead and underground power lines. Obtain further information at: **http://www.torontohydro.com/powerlinesafety**

TORONTO MUNICIPAL CODE 441
FEES AND CHARGES
Appendix C - Schedule 8, Toronto Building

25 256572 BLD 00 SR
173 WOBURN AVE

Total Permit Fee $1,632.92

Work Proposed *New Laneway / Rear Ya* **Sub** *Laneway / Rear Yard Suite*

Building Classification	Service Index *Dollars per Square Meter unless otherwise indicated*	Value in Square Meters *(unless otherwise indicated)*	Fee
A. Construction:			
Group C (Residential Occupancies):			
Single family dwellings, semis, townhouses, duplexes, live-work units - All other residential occupancies	17.85	91.48	1,632.92

Total Permit Fee **$1,632.92**

TORONTO

Permit Advisory Notes

Building permits issued under subsection 8(2) of the Building Code Act, 1992 (the "BCA") have been reviewed for compliance with the BCA, the Ontario Building Code 2024, and "applicable law", as that term is defined in Sentence 1.4.1.3(1) of Division A of the Ontario Building Code. There may be other approvals that you require to carry out the construction and/or demolition authorized by the building permit. The following advisory notes flag for you some of the other approvals that are frequently required to proceed with construction and/or demolition like that authorized by the building permit. These advisory notes are not meant to provide you with an exhaustive list of other approvals that may be required, and you must therefore satisfy yourself that you have obtained all other applicable approvals prior to commencing the construction and/or demolition authorized by the building permit.

- [ ] Permit issuance does not authorize encroachments onto adjacent property.

- [ ] This building permit is separate and distinct from any approval required to discharge groundwater to the City Sewer System. As such, this building permit does not relieve the permit holder of the need to seek approvals from Environmental Monitoring & Protection Unit of Toronto Water, prior to carrying out any de-watering on the site.
If a Permit to Discharge Groundwater to the City Sewer System is not approved, and de-watering is required as part of the associated design the shoring system and/or foundation system may need to be redesigned to accommodate hydrostatic pressure.

- [ ] This building permit is separate and distinct from any approval required in association with the removal of a tree(s) or any work associated with either private or public utility infrastructure, as identified in the documentation submitted to Toronto Building by the permit applicant. As such, this building permit does not relieve the permit holder of the need to seek approvals from the appropriate City Division or external agency, as applicable, prior to carrying out any construction authorized by this permit.

- [ ] Permit issuance does not include the authority to enter on adjacent property. Refer to City of Toronto Muncipipal Code, Chapter 363 - Building Construction and Demolition, Article V, Right of Entry, for requirements to allow access onto adjacent property.

EXCAVATION NOTE:

The issuance of this building permit does not create or provide you with any property rights or authority to enter onto, encroach, alter, or damage any adjacent real property. More specifically, this building permit does not authorize any excavation on the adjacent real property. Further, unless you have the legal rights to do otherwise, evidenced separately and apart from this building permit which grants no such rights, every excavation shall be undertaken in such a manner as to prevent damage to adjacent property, existing structures, utilities, roads and sidewalks at all stages of construction. Proper evaluation, care, and practices, including assessment of the soil and soil quality and the consideration of the need for shoring, must be used in preparing for and carrying out any excavations. If shoring is required, you must submit drawings with clear design parameters for review and approval under a revised permit application. A geotechnical report and structural calculations must be included in your permit submission.

THE LATEST VERSION OF THE BUILDING CODE OVERRULES WHERE DISCREPANCY FOUND BETWEEN GENERAL NOTES AND BUILDING CODE

Note: The contents of General Notes and Details' Specifications (Both structural & architectural) must comply with all Building Code requirements and other standards and regulations. This is the role of owner, designer, and builders to construct the building in accordance with the Building Code and other related standards. (Building Code Act subsections 1.1.(1), 1.1.(2) and 1.1.(3)).

The construction between the garage and the dwelling unit: an air barrier system conforming to Subsection 9.25.3. shall be installed between the garage and the remainder of the building to provide an effective barrier to gas and exhaust fumes. A door between the garage and the dwelling shall be tight fitting, weather stripped and fitted with a self-closing device.
Such door shall not open into a bedroom.

Building Permit 332_12

The reviewed plans and specifications must be available on site during construction/demolition. Changes to these plans and specifications are not to be made unless prior written approval is obtained from the Chief Building Official.

The owner/permit holder is required to comply with the following Permit Notes, which are part of the reviewed permit documents:

- [ ] Access to attic and crawl space minimum 545mm x 700mm insulated and weather-stripped.

- [ ] Brick veneer ties to be hot-dipped galvanized.

- [ ] Buried Water Service Pipe shall, except as permitted in Article 7.3.5.7. of the OBC, a buried water service pipe shall be separated from the building drain, building sewer and a private sewage disposal system, by not less than 2 440 mm (8 ft) measured horizontally, of undisturbed or compacted earth.

- [ ] Carbon monoxide detector conforming with CAN/CGA-6.19, or UL2034 shall be installed on or near the ceiling in each room in which there is installed a solid fuel-burning appliance. Carbon monoxide detector(s) shall be wired so that its activation will activate the smoke alarms or be equipped with an alarm that is audible within bedrooms when the intervening doors are closed.

- [ ] Standards referenced in Section 1.3 of Division B shall be complied with Table 1.3.1.2.:
  a) Wood - CAN/CSA- O86-01
  b) Plain and Reinforced Masonry - CAN-S304-M or CSA-S304.1
  c) Plain, reinforced and Pre-stressed Concrete - CAN/CSA-23.3, CAN/CSA A23.1, CAN/CSA A23.2
  d) Structural Steel - CAN/CSA-S16-01
  e) Parking Structures - CSA-S413

- [ ] Drain Water Heat Recovery units shall be provided for showers in accordance with Supplementary Standard SB-12, Article 3.1.1.12.

- [ ] 1. Where gravity drainage is not practical, a covered sump with an automatic pump shall be installed to discharge the water into a sewer**, drainage ditch or dry well
  2. Dry wells are permitted to be used only when located in areas where the natural groundwater level is below the bottom of the dry well.
  3. Dry wells shall be not less than 5m (16 ft 5in) from the building foundation and located so that drainage is away from the building
  ** Toronto Municipal Code, Chapter 681 prohibits the drainage discharge into a sewer.

- [ ] Eave Protection is required from edge of the roof a minimum distance 900mm up the roof slope to not less than 300mm inside the inner face of the exterior wall on shingled, shake or tile roofs. Eave protection shall be laid beneath the start strip.

- [ ] Excavations that exceed 1.2 m are required to be shored or cut back at the top so that the angle of the cut does not exceed 1:1. If shoring is to be provided submit drawings with design parameters clearly stated for approval under separate permit application. A soil report and/or calculations may be requested.

- [ ] Exterior Concrete for garage slabs, porches and exterior steps shall have a minimum compressive strength at 28 days is 32MPa and 5% to 8% air entrainment.

- [ ] Foamed insulation shall be protected on interior surfaces by gypsum board or equivalent.

- [ ] Entrance doors to dwelling units shall comply with subsection 9.6.8. "Resistance to forced entry"; windows, any part of which is located within 2m (6ft. 7in.) of adjacent ground level, shall conform to the requirements for resistance to forced entry as described in clause 10.13 of CSA Standard A440-M90 "Windows";

- ☑ The direct connection of the groundwater drainage system to a municipal sewer is prohibited for new and reconstructed residential buildings as per Toronto Municipal Code Chapter 681. Owners may make application to the General Manager of Toronto Water for an exemption from this restriction on municipal sewer connections where there is no practical alternative means of discharging drainage water.

- ☑ OBC 9.14.5.1. requires foundation drains to drain to a sewer, drainage ditch or dry well. Where gravity drainage is not practical, a covered sump with an automatic pump shall be installed to discharge the water into a sewer, drainage ditch or dry well.

- ☑ Foundation walls shall be adequately braced or laterally supported prior to backfill.

- ☑ For reduced foundation walls to allow brick facing and maintain lateral support:
Tie bricks to block with 5mm diameter ties or equal, or tie to concrete with 1.52mm x 25mm dovetail masonry ties. Ties to be spaced at 200mm o/c. vertical and 900mm o/c. horizontal. Fill space between brick and foundation wall with mortar.
Reduced block or concrete thickness shall be not less than 90mm.

- ☑ Guards shall comply with appropriate detail from SB-7 of the Supplementary Standards to the Ontario Building Code, or comply to the loading criteria in Article 9.8.8.2.
Guards shall have openings not greater than 100 mm unless permitted under article 9.8.8.5. and not be climbable as per article 9.8.8.6.

- ☑ Exposed stud exterior walls under the floor of a habitable room above a garage must be covered on the inside with a fume-tight membrane such as gypsum board taped and sealed.

- ☑ Every floor level containing bedrooms shall be provided with at least one outside openable window with an individual unobstructed opening having a minimum area of 0.35 sq. m with no dimension less than 380 mm. Except for basements, the window shall have a maximum sill height of 1m above the floor.

- ☑ Except for doors on enclosed unheated vestibules and cold cellars, and except for glazed portions of doors, all doors that separate heated space from unheated space shall have a thermal resistance (performance) of not less than RSI 0.7 where a storm door is not provided. All sliding glass doors that separate heated space from unheated space shall have an energy rating of not less than 17 as per article 12.3.2.7. of Division B.

- ☑ Thermal resistance (performance) for all windows that separate heated space from unheated space shall have an energy rating of not less than 17 for operable windows units and not less than 27 for fixed windows units. Exception: basement windows with loadbearing structural frame shall be double glazed with low-E coating as per article 12.3.2.6. of Division B.

- ☑ The City has Relied upon the plans and drawings prepared and submitted by the qualified architects and/or engineers on this project.

  The issuance of a permit does not imply a complete design review of this project has been performed and does not relieve the owner and designers from the need to comply with the Ontario Building Code and referenced standards where contravention are subsequently noted.

TORONTO

- [ ] 1. Pre-Engineered roof trusses shall be designed for the following superimposed specified loads:
Top chord: Dead Load = 0.29 kPa or appropriate load; and Live Load, or Snow Load = 1.00 kPa, except Snow Load = 1.06 kPa for North York and Scarborough.
Bottom chord: Minimum (Dead Load + Live Load) = 0.35 kPa for space with limited accessibility that precludes storage, otherwise Live Load = 1.4 kPa + appropriate Dead Load ; trusses outside the scope of 2012 OBC Div B - Part 9 prescriptive requirement, shall have bottom chord designed for appropriate Part 4 Live Load.
2. Trusses tested or analyzed in conformance with Part 9 - 9.23.13.11.(1) to (6) shall be deemed capable of sustaining the design loads specified above.
3. Prior to commencement of truss erection, submit to the building inspector 1 copy of the wood roof truss shop drawings bearing the seal and signature of a Professional Engineer, Ontario.

- [ ] Roof vent areas to be 1/300 of the insulated ceiling area. For cathedral ceilings or for roof slopes less than 1 in 6, vent areas to be 1/150 of insulated ceiling area. Vents to be uniformly distributed.

- [ ] HVAC and PLUMBING are not part of this permit approval.

- [ ] Shop Drawings shall be submitted for the following item(s), as indicated, for review by theToronto Building Division prior to erection or installation:
[ ]STEEL JOISTS & TRUSSES
[ ]STRUCTURAL STEEL ERECTION
[ ]FIRE ESCAPE & STEEL STAIRS
[ ]PRECAST CONCRETE SYSTEMS
[ ]RAILINGSS
[ ]SPRINKLERS

- [ ] Smoke alarms conforming to ULC-S531, shall be provided on each floor level in accordance with article 9.10.19.2. Smoke alarms shall be installed near the stairs except, on floors containing sleeping areas the smoke alarms shall be installed between the sleeping areas and the remainder of the floor area. Where more than one smoke alarm is required, they shall be interconnected.

- [ ] Footings shall rest on natural undisturbed stable soil or compacted granular fill with a minimum soil bearing capacity of 75 kPa

- [ ] Step footings for soil with soild bearing capacity of 75KPa: max. rise 600 mm min. run 600mm.

- [ ] In compliance with Sentence 9.14.6.1 the building site shall be so graded that discharged water will not accumulate at or near the building and will not adversely affect adjacent properties.

- [ ] All structural wood elements shall be protected against termites and decay as per provisions of 9.3.2.9.

- [ ] The construction between the garage and the dwelling unit shall provide an effective barrier to gas and exhaust fumes. A door between the garage and the dwelling shall be tight fitting, weather stripped and fitted with a self closing device. Such door shall not open into a bedroom. A clear parking space shall be provided with no encroachment (such as steps) into this space.

- [ ] Rooms and spaces in residential buildings shall be naturaly ventilated in accordance with 9.32.2. or mechanically ventilated in accordance with 9.32.3."

Above notes are referring to the OBC 2012 requirements.
This is the responsibility of the owner, designer, and contractor to apply the equivalent requirements of OBC 2024.

GENERAL NOTES

Capping & Parging to be done in compliance with the OBC 9.15.5.1., 9.15.6.1.

Sill plate anchorage & levelling to be performed in compliance with the OBC requirement 9.23.7.2.(1), 9.23.6.1.(2) & (3).

Wall sheathing to comply with the OBC 9.23.17.1. & 9.23.17.2.

Roof sheathing to comply with 9.23.16. for roof used as walking deck & Tables 9.23.15.5. A & B for thickness or rating of flat roofs.

Subflooring shall be provided beneath finish flooring where the finish flooring does not have adequate strength to support the design loads in compliance with the OBC requirement 9.23.15.

Exterior wall sheathing to comply with the OBC 9.27.3.

Dampproofing to comply with the OBC 9.13.2.

Drainage tile and stone cover to be provided in compliance with the OBC 9.14.2., 9.14.3. & 9.14.4.

Floor Drain is required in compliance with 9.31.4.3.

Air & Vapor barriers to comply with 9.25.3., 9.25.4.

Fire blocks to be provided in compliance with the OBC subsection 9.10.16.

Door and window sizes to comply with Table 9.5.5.1.& Table 9.7.2.3. and Table 9.32.2.2.

Stucco cladding to comply with the OBC Section 9.28.

Flashing material and weep holes for masonry brick cladding to comply with the OBC subsection 9.20.13.

For exterior stairs have more than three risers and serving a house to provide handrail OBC 9.8.7.1.(3)

Entrance doors to dwelling units shall comply with 9.7.5.2. Resistance to forced entry.

Mechanical Ventilation to be provided for the proposed washrooms when natural ventilation is not provided in compliance with the OBC Table 9.32.2.2.

Strapping and bridging to be provided in compliance with OBC requirement 9.23.9.4.

Where a chimney is proposed in the design, it shall comply with OBC section 9.21 especially 9.21.4.4.

Interior and exterior stair landings to comply with the OBC – Subsection 9.8.6.

OBC Div B. 9.13.4.2.(2): Unless the space between the air barrier system and the ground is designed to be accessible for the future installation of a subfloor depressurization system, dwelling units and buildings containing residential occupancies shall be provided with the rough-in for a radon extraction system conforming to Article 9.13.4.3.

Structural sufficiency and thickness of the glasses to comply with the requirement of OBC 9.6.1.3.

All handrails and guards must comply with SB-7 and OBC 9.8.7 & 9.8.8. (typ.). Guards shall have openings not greater than 100mm unless permitted and not climbable as per article 9.8.8.6. & 9.8.8.2. (2).
(Glass) handrails and guards: all handrails and guards must comply with SB-7, SB-13 and OBC 9.8.8. (typ.)

TERMITE PROTECTION: When wood is required to be treated to resist termites or decay it should in compliance with the OBC 9.3.2.9. & Table 2 of “Use Categories for Specific Products, Uses, and Exposures”, of CAN/CSA-O80.1, “Specification of Treated Wood.”

Where adjacent building’s footing undermined due to excavation on this property, engineer to field review, prior to shoring and excavation to determine the exact location of adjacent buildings' footings and confirm adjacent building will not be adversely affected and all assumptions made through the design process including soil parameters and surcharge loads are valid also, provide general review during shoring activity and submit verification report the Toronto building inspector at the end of shoring construction.

TORONTO

Application

Commitment to General Reviews

Folder No.

District Offices

☐ Toronto and East York ☐ North York ☐ Scarborough ☐ Etobicoke York

PART A – To be Completed by Owner

Project Description

CONSTRUCT A NEW GARAGE / LANEWAY HOME

Project Address (Street Number, Street Name, Suite/Unit Number, City/Town, Postal Code)
173 WOBURN AVE, TORONTO, ONTARIO, M5M 1K8

WHEREAS the Ontario Building Code requires that the project described above be designed and reviewed during construction or demolition by an architect, professional engineer or both that are licensed to practice in Ontario;
WHEREAS Ontario Law prohibits the construction or demolition of a building if a permit has not been issued to authorize it, and
WHEREAS Architects and engineers are prohibited by law from undertaking reviews if a permit has not been issued,
NOW THEREFORE the Owner, who intends to construct or demolish or have the building constructed or demolished hereby confirms that:

1. The undersigned architect and/or professional engineers have been retained to provide general reviews of the construction or demolition of the building to determine whether the work is in general conformity with the plans and other documents that form the basis for the issuance of a permit, in accordance with the performance standards of the Ontario Association of Architects (OAA) and/or Professional Engineers of Ontario (PEO);
2. All general review reports by the architect and/or professional engineers will be forwarded promptly to the Chief Building Official;
3. Should any retained architect or professional engineer cease to provide general reviews for any reason during construction or demolition, the Chief Building Official will be notified in writing immediately, and another architect or engineer will be appointed so that general review continues without interruption; and
4. Construction or demolition will only be undertaken if an architect and/or professional engineers are retained to undertake general review, and a permit authorizing the proposed construction or demolition has been issued.

The undersigned hereby certifies that he/she has read and agrees to the above.

Owner's First Name NICOLA & SANDRA		Last Name SACCONE	
Street Number 103	Street Name GLEN LONG AVE		Postal Code M6B 2M4
Telephone Number	Mobile Number 416-829-3256	Fax Number	

DocuSigned by:
DCB098...

DocuSigned by:
Sandra Saccone
98FC59C6A479492...

Signature | NICK & SANDRA SACCONE
Print Name | 2025-11-05
Date (yyyy-mm-dd)

Co-ordinator of the work of all consultants

Street Number	Street Name		Postal Code
Telephone Number	Mobile Number	Fax Number	

Continue on next page

The personal information on this form is collected under the City of Toronto Act, S.O. 2006, Chapter 11, Schedule A, s. 136 (c) and the Building Code Act, S.O. 1992, Chapter 23, s. 8(1) and (2). The information collected will be used for processing applications and creating aggregate statistical reports. Questions about this collection may be referred to the Customer Service Manager in the appropriate district. Toronto East York District, 100 Queen Street West, Ground Floor, West Tower, Toronto M5H 2N2; North York District, 5100 Yonge Street, 1st Floor, Toronto M2N 5W4; Etobicoke York District, 2 Civic Centre Court, 1st Floor, Toronto M9C 2Y2; Scarborough District, 150 Borough Drive, 3rd Floor, Toronto M1P 4N7 or by telephone at (416) 397-5330.

Application

Commitment to General Reviews

PART B – To be completed by Consultants

The undersigned architect and/or professional engineer(s) hereby certify that they are qualified in and have been retained to provide general reviews of the parts of construction or demolition of the building indicated, to determine whether the work is in general conformity with the plans and other documents that form the basis for the issuance of a permit, in accordance with the performance standards of the Ontario Association of Architects (OAA) or Professional Engineers Ontario (PEO).

First Consultant Information and Declaration

☐ Architectural ☑ Structural ☐ Mechanical ☐ Electrical ☐ Site Services

☐ Other:

First Name	Last Name	Firm
BEN	TORKAN	

Street Number	Street Name	Postal Code

Telephone Number	Mobile Number	Fax Number
6474530711	647-453-0711	

Signature	Print Name	Date (yyyy-mm-dd)
[signature]	BEN TORKAN	2025-11-19

Second Consultant Information and Declaration (if applicable)

☐ Architectural ☐ Structural ☐ Mechanical ☐ Electrical ☐ Site Services

☐ Other:

First Name	Last Name	Firm

Street Number	Street Name	Postal Code

Telephone Number	Mobile Number	Fax Number

Signature	Print Name	Date (yyyy-mm-dd)

Third Consultant Information and Declaration (if applicable)

☐ Architectural ☐ Structural ☐ Mechanical ☐ Electrical ☐ Site Services

☐ Other:

First Name	Last Name	Firm

Street Number	Street Name	Postal Code

Telephone Number	Mobile Number	Fax Number

Signature	Print Name	Date (yyyy-mm-dd)

Where adjacent building's footing undermined due to excavation on this property, engineer to field review, prior to shoring and excavation to determine the exact location of adjacent buildings' footings and confirm adjacent building will not be adversely affected and all assumptions made through the design process including soil parameters and surcharge loads are valid also, provide general review during shoring activity and submit verification report the Toronto building inspector at the end of shoring construction.

Energy Efficiency Design Summary: Prescriptive Method

(Building Code Part 9, Residential)

This form is used by a designer to demonstrate that the energy efficiency design of a house complies with the building code using the prescriptive method described in Subsection 3.1.1. of SB-12. This form is applicable where the ratio of gross area of windows/sidelights/skylights/glazing in doors and sliding glass doors to the gross area of peripheral walls is not more than 22%.

For use by Principal Authority	
Application No:	Model/Certification Number

A. Project Information

Building number, street name	Unit number	Lot/Con
173 Woburn Avenue		

Municipality	Postal code	Reg. Plan number / other description
Toronto		

B. Prescriptive Compliance [indicate the building code compliance package being employed in this house design]

SB-12 Prescriptive (input design package): Package: A1 Table: 3.1.1.2.A (IP)

C. Project Design Conditions

Climatic Zone (SB-1):	Heating Equipment Efficiency	Space Heating Fuel Source		
X Zone 1 (< 5000 degree days)	X ≥ 92% AFUE	X Gas	☐ Propane	☐ Solid Fuel
☐ Zone 2 (≥ 5000 degree days)	☐ ≥ 84% < 92% AFUE	☐ Oil	☐ Electric	☐ Earth Energy

Ratio of Windows, Skylights & Glass (W, S & G) to Wall Area		Other Building Characteristics
Area of walls = ____ m^2 or 1058.5 ft^2	W, S & G % = 3.40	☐ Log/Post&Beam ☐ ICF Above Grade ☐ ICF Basement X Slab-on-ground ☐ Walkout Basement X Air Conditioning ☐ Combo Unit
Area of W, S & G = ____ m^2 or 36.0 ft^2	Utilize window averaging: ☐Yes X No	☐ Air Sourced Heat Pump (ASHP) ☐ Ground Sourced Heat Pump (GSHP)

D. Building Specifications [provide values and ratings of the energy efficiency components proposed]

Energy Efficiency Substitutions

☐ ICF (3.1.1.2.(5) & (6) / 3.1.1.3.(5) & (6))

☐ Combined space heating and domestic water heating systems (3.1.1.2.(7) / 3.1.1.3.(7))

☐ Airtightness substitution(s)			
Airtightness test required (Refer to Design Guide Attached)	☐ Table 3.1.1.4.B	Required:	Permitted Substitution:
	☐ Table 3.1.1.4.C	Required:	Permitted Substitution:
		Required:	Permitted Substitution:

Building Component	Minimum RSI / R values or Maximum U-Value(1)		Building Component	Efficiency Ratings	
Thermal Insulation	Nominal	Effective	**Windows & Doors** Provide U-Value(1) or ER rating		
Ceiling with Attic Space	R60		Windows/Sliding Glass Doors	0.28	
Ceiling without Attic Space	R31		Skylights/Glazed Roofs	0.49	
Exposed Floor	R31		**Mechanicals**		
Walls Above Grade	R22		Heating Equip.(AFUE)	96 %	
Basement Walls (R12+10ci)	R20ci		HRV Efficiency (SRE% at 0°C)	75 %	
Slab (all >600mm below grade)	R-		DHW Heater (EF)	0.80	
Slab (edge only ≤600mm below grade)	R10		DWHR (CSA B55.1 (min. 42% efficiency))	42 %	# Showers 1
Slab (all ≤600mm below grade, or heated)	R10		Combined Heating System		

(1) U value to be provided in either W/(m^2•K) or Btu/(h•ft^2•F) but not both.

E. Designer(s) [name(s) & BCIN(s), if applicable, of person(s) providing information herein to substantiate that design meets the building code]

Qualified Designer Declaration of designer to have reviewed and take responsibility for the design work.

Name	BCIN	Signature
Enzo Franzese Franzese Mechanical Ltd.	BCIN 26559 BCIN 35010	

Form authorized by OHBA, OBOA, LMCBO. Revised December 1, 2016.

Where adjacent building's footing undermined due to excavation on this property, engineer to field review, prior to shoring and excavation to determine the exact location of adjacent buildings' footings and confirm adjacent building will not be adversely affected and all assumptions made through the design process including soil parameters and surcharge loads are valid also, provide general review during shoring activity and submit verification report the Toronto building inspector at the end of shoring construction.

This application has been reviewed in conjunction of the registered Limiting Distance Agreement between 173 & 171 Woburn Ave



SITE PLAN

PART 1 – PLAN OF SURVEY OF

LOT 596

REGISTERED PLAN M-107

CITY OF TORONTO

SCALE 1:100

7.5m 3.75 0 7.5 METRES

METRIC

DISTANCES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048

LEGEND

□	DENOTES MONUMENT SET
■	DENOTES MONUMENT FOUND
SIB	DENOTES STANDARD IRON BAR
IB	DENOTES IRON BAR
P1	DENOTES PLAN OF SURVEY BY SPEIGHT VAN NOSTRAND, O.L.S. DATE DECEMBER 15, 1927
RP	DENOTES REGISTERED PLAN M-107
D	DENOTES INST. No. B95314
PIN	DENOTES PROPERTY IDENTIFIER NUMBER
M	DENOTES MEASURED
N,S,E,W	DENOTES NORTH, SOUTH, EAST, WEST
B.F.	DENOTES BOARD FENCE
NI	DENOTES NOT IDENTIFIABLE
OU	DENOTES ORIGINAL UNKNOWN
F.F.E.	DENOTES FINISHED FLOOR ELEVATION AT ENTRY
O.H.W.	DENOTES OVERHEAD WIRE
STO.	DENOTES TIE TAKEN FROM STONE
STC.	DENOTES TIE TAKEN FROM STUCCO
F.H.	DENOTES FIRE HYDRANT
M.H.	DENOTES MANHOLE
U.P.	DENOTES UTILITY POLE
U.P.L.S.	DENOTES UTILITY POLE WITH LIGHT STANDARD
W.V.	DENOTES WATER VALVE
C.B.	DENOTES CATCH BASIN
	DENOTES CONIFEROUS TREE
	DENOTES DECIDUOUS TREE

SUMMARY OF AREAS

PROPOSED R7 – ZONE	SQ.M.	SQ.FT.	%
EXISTING HOME COVERAGE/GFA			
LOT AREA	232.23	2499.70	
EXISTING AREA (BASMT NOT INCLUDED)	221.95	2389.05	95.57%
EXISTING COVERAGE	87.91	946.30	37.85%
PROPOSED GARAGE/ COACH HOUSE COVERAGE/GFA			
FLOOR AREAS:			
GARAGE FLOOR AREA	39.95	430.03	
2ND FLOOR AREA	45.74	492.41	
TOTAL FLOOR AREA	85.69	922.44	
LOT AREA	232.23	2499.70	
PROPOSED AREA (INCLD. GARAGE, BASMT NOT INCLUDED)	85.69	922.44	36.90%
PROPOSED COVERAGE	45.74	492.41	19.70%

No.	Date	Revisions / Issues	
7	DEC 7–25	LIMITED DISTANCE	NS
6	DEC 7–25	FIRE ACCESS ROUTE ADDED	NS
5	NOV 10–25	ISSUED FOR BUILDING PERM.	NS
4	OCT 22–25	ISSUED FOR ZONING CERTIF.	NS
3	AUG 19–25	ISSUED FOR ZONING REVIEW	NS
2	JULY 14–25	ISSUED TO C of A	NS
1	OCT 08–24	ISSUED FOR CLIENT REVIEW	NS

LICENSED PROFESSIONAL ENGINEER
B. TORKAN
100142000
11/17/2025
PROVINCE OF ONTARIO

Project
173 WOBURN AVE
TORONTO, ONTARIO

Title
SITE PLAN

TRADEMARKED BY DESIGN INC.
YOUR DREAM IS MY VISION...
TEL: (416) 829-3256 103 GLEN LONG AVE
FAX: (416) 783-9042 TORONTO, ONT. M6B 2M4
E-mail: trademarkedbydesign@yahoo.ca

DOMESTIC COLD WATER AND SANITARY SEWER CONNECTIONS FOR LANEWAY/GARDEN SUITES

The domestic cold-water pipe for the laneway/garden suite shall be serviced from the principal building. The water supply shall connect to the water piping immediately downstream of the water meter located in the principal building. The water pipe shall be routed via the shortest path to the exterior of the principal building to minimize encroachment on the living space within the principal building. The water pipe shall run underground to the laneway /garden suite. A shut off valve shall be provided on the water pipe connection downstream of the water meter and on the water pipe entering the laneway/garden suite.

The sanitary sewer for the laneway/garden suite shall be connected to the same sewer servicing the principal building. The connection to the existing sanitary sewer shall be made upstream of the principal building. The sewer shall not run below the basement of the principal building to conform to OBC Div. B, 7.1.5.4.(4).

Requirements for frost protection, cleanouts, piping material shall be in accordance with Part 7 of OBC.

ACCESS PATH NOTES:

1. Access paths from the street to the front door of the laneway suite or garden suite shall be constructed of concrete, asphalt, brick, or alternate hard surface.
2. Gradient changes, including stairs, are Building Code compliant.
3. No locked gates along path of travel
4. The horizontal path of travel permits the transport of a 24-foot extension ladder (collapsed length – 12 feet for a smooth path of travel to navigate and avoid any sharp turning radius).
5. Access paths must remain unobstructed and clear of snow and ice.

Where a building is constructed in close proximity to above ground electrical conductors, the building must meet the clearance requirements of Article 3.1.20.1 of Division B of the Ontario Building Code. For detailed information, please refer to Toronto Hydro's clearance guides at https://www.torontohydro.com/for-business/make-a-service-requests.

The City has relied upon the plans and drawings prepared and submitted by the owner and his designers on this project. The issuance of a permit does not relieve the owner and designers from the need to comply with the Building Code and referenced standards where contravention is subsequently noted.

At least one egress window shall be provided in the basement suite in compliance with OBC 9.9.10.1.:
a) Is openable from the inside without the use of tools
b) Provides an individual, unobstructed open portion having a minimum area of 0.35 m² with no dimension less than 380 mm, and
c) Maintains the required opening described in Clause (b) without the need for additional support.

Where the permit drawings and/or documents bear the seal of a professional engineer, no or limited review was carried out by Toronto Building to confirm that the matters to which the seal relates comply with the Ontario Building Code. As the seal denotes assumption of responsibility by the professional engineer, compliance with the Ontario Building Code was determined in whole or in part by reasonably relying solely on the seal of the professional engineer. Permit issuance does not absolve the owner or designers from ensuring compliance with the Ontario Building Code and applicable standards.

THE LATEST VERSION OF THE BUILDING CODE OVERRULES WHERE DISCREPANCY FOUND BETWEEN GENERAL NOTES AND BUILDING CODE

Schedule C drawing for LDA



SCHEDULE C DRAWING FOR LDA

FIRE DEPARTMENT ACCESS VIA PROPERTY

SCALE 1:100

7.5m 3.75 0 7.5 METRES

METRIC

DISTANCES SHOWN ON THIS PLAN ARE IN METRES AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048

N

LIMITING DISTANCE AREA

TORONTO Building

PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE

25 256572 BLD 00

ZONING		
O.B.C.		
FIRE SERVICES		

O.B.C. (S)

TYPICAL CONSTRUCTION NOTES

1. ROOF CONSTRUCTION
2 PLY CAN'T MEMBRANE, TORCHED ON 15.8mm (5/8") EXT. PLYWOOD SHEATHING WITH "H" CLIPS. APPROVED WOOD TRUSSES @ 600mm (24") O.C. MAX. APPROVED EAVES PROTECTION TO EXTEND 900mm (3'-0") FROM EDGE OF ROOF AND MIN. 300mm (12") BEYOND INNER FACE OF EXTERIOR WALL, 38x89 (2"x4") TRUSS BRACING @ 1830mm (6'-0") O.C. AT BOTTOM CHORD. PREFIN. ALUM. EAVESTROUGH, FASCIA, RWL & VENTED SOFFIT. ATTIC VENTILATION 1:300 OF INSULATED CEILING AREA WITH 50% AT EAVES.

2. NON -COMBUSTIBLE FRAME WALL CONSTRUCTION
LESS THAN 600mm FROM LOT LINE
SIDING AS PER ELEVATION, 8" CONC. BLK
15M RE BAR 400mm (16") O.C.
PROVIDE BLOCK LOCK EVERY SECOND COURSE

2A. ♦ NON -COMBUSTIBLE FRAME WALL CONSTRUCTION
SIDING AS PER ELEVATION,
6" CONC. BLK
38x89 (2"x4") STUDS @ 400mm (16") O.C.
RSI 4.22 (R24) BATT INSULATION OR SPRAY FOAM AND APPROVED VAPOUR BARRIER CONT.
13mm (1/2") INT. DRYWALL FINISH.

3A. COMBUSTIBLE FRAME WALL CONSTRUCTION (2"x6")
LESS THAN 600mm FROM LOT LINE
SIDING AS PER ELEVATION,
38x140 (2"x6") STRUCT. METAL STUDS @ 400mm (16") O.C.,
12.7mm (1/2") CEMENT BOARD,
RSI 4.22 (R24) BATT INSULATION AND APPROVED VAPOUR BARRIER OR 2LBS SPRAY FOAM
13mm (1/2") INT. DRYWALL FINISH.
5/8" TYPE 'X' WHEN LESS THAN 1.2M FROM LOT LINE

3B. ♦ COMBUSTIBLE FRAME WALL CONSTRUCTION (2"x6")
MORE THAN 600mm FROM LOT LINE
SIDING AS PER ELEVATION, APPROVED SHEATHING PAPER, 12.7mm (1/2") EXT. TYPE SHEATHING,
38x140 (2"x6") STUDS @ 400mm (16") O.C.,
RSI 4.22 (R24) BATT INSULATION AND APPROVED VAPOUR BARRIER
13mm (1/2") INT. DRYWALL FINISH.
5/8" TYPE 'X' WHEN LESS THAN 1.2M FROM LOT LINE

4. INTERIOR STUD PARTITIONS
-BEARING PARTITIONS 38x89 (2"x4") @ 400mm (16") O.C. FOR 2 STOREYS AND 300mm (12") O.C. FOR 3 STOREYS. NON-BEARING PARTITIONS 38x89 (2"x4") @ 600mm (24") O.C.. PROVIDE 38x89 (2"x4") BOTTOM PLATE AND 2/38x89 (2-2"x4") TOP PLATE. 13mm (1/2") INTERIOR DRYWALL BOTH SIDES OF STUD, PROVIDE 38x140 (2"x6") STUDS/PLATES WHERE NOTED.

4A. 1 HR INTERIOR STUD PARTITIONS
3/4" TYPE "X" GYPSUM BOARD
2"x6" STUDS (OR AS NOTED) @16" OC,
DOUBLE TOP PLATE
50 STC SOUND INSULATION
3/4" TYPE "X" GYPSUM COARD,
TAPED AND SANDED FOR PAINTING
10

5. FOUNDATION WALL/FOOTINGS:
10" POURED CONCRETE FOUNDATION WALL
REINFORCE FOUNDATION WALL
15M VERTICAL 16" O.C., 15 HORIZON. 16" O.C.
DAMPROOFING WITH DRAINAGE LAYER. PROVIDE
PROVIDE PARGING COVER ON 550x200 (22"x8")
EMBED 15M DOWELS @ 32" O.C,. CONC. FTG.
BRACE FOUNDATION WALL
PRIOR TO BACKFILLING. ALL FOOTINGS SHALL REST ON NATURAL UNDISTURBED SOIL OR COMPACTED ENGINEERED FILL, WITH MINIMUM BEARING CAPACITY OF 75kPa OR GREATER.

6. 100mm (4") DIA. WEEPING TILE 150mm (6") CRUSHED STONE OVER AND AROUND WEEPING TILES.

7. ♦ BASEMENT SLAB
90mm (3 1/2")MIN. 25MPa (3600psi) CONC. SLAB ON 50MM (2") RIDGE INSULATION R10, ON 100mm (4") COARSE GRANULAR FILL, OR 15MPa (2200psi) CONC. WITH DAMPPROOFING

8. ♦ EXPOSED FLOOR TO EXTERIOR
PROVIDE RSI 5.5 (R31) INSULATION, APPROVED VAPOUR BARRIER AND CONTINUOUS AIR BARRIER, FINISHED SOFFIT.

9. ♦ RSI 5.5 (R31) 2LB SPRAY FOAM ROOF INSULATION HOT ROOF, MECHANICAL VENTILATION TO BE PROVIDED 12mm (1/2") DRYWALL FINISH OR APPROVED EQUAL.

10. ♦ ALL STAIRS/EXTERIOR STAIRS -OBC. 9.8.-

MAX. RISE	= 200 (7-7/8")
MIN. RUN	= 255 (10")
MIN. TREAD	= 235 (9-1/4")
MAX. NOSING	= 25 (1")
MIN. HEADROOM	= 1950 (6'-5")
RAIL @ LANDING	= 900 (2'-11")
RAIL @ STAIR	= 800 (2'-8")
MIN. STAIR WIDTH	= 860 (2'-10")

FOR CURVED STAIRS

MIN. RUN NARROW END	= 150 (6")
MIN. RUN	= 255 (10")

11. ♦ FINISHED RAILING ON PICKETS SPACED MAXIMUM 100mm (4") BETWEEN PICKETS.
GUARDS -OBC. 9.8.8.2.-
INTERIOR GUARDS: 900mm (2'-11") MIN.
EXTERIOR GUARDS: 1070mm (3'-6") MIN.

12. 38x140 (2"x6") SILL PLATE WITH 13mm (1/2") DIA. ANCHOR BOLTS 200mm (8") LONG, EMBEDDED MIN. 100mm (4") INTO CONC. @ 2400mm (7'-10") O.C., CAULKING OR 25mm (1") MIN. MINERAL WOOL BETWEEN PLATE AND TOP OF FDTN. WALL. USE NON-SHRINK GROUT TO LEVEL SILL PLATE WHEN REQUIRED.

13. ♦ RSI 3.25 (R20) C.I. INSULATION. WITH 38x89 (2"x4") STUD WALL, AND APPROVED VAPOUR BARRIER FULL HEIGHT OF BASEMENT WALLS. DAMPPROOF W/ BLDG. PAPER BETWEEN THE FDTN. WALL AND INSUL. REFER TO DETAIL "I"

14. ♦ BEARING STUD PARTITION
38x150 (2"x6") STUDS @ 400mm (16") O.C. 38x150 (2"x6") SILL PLATE ON DAMPPROOFING MATERIAL, 13mm (1/2") DIA. ANCHOR BOLTS 200mm (8") LONG, EMBEDDED MIN. 100mm (4") INTO CONC. @ 2400mm (7'-10") O.C. 100mm (4") HIGH CONC. CURB ON 350x155 (14"x6") CONC. FOOTING. ADD HORIZ. BLOCKING AT MID-HEIGHT IF WALL IS UNFINISHED.

15. ♦ STEEL COLUMN (SEE O.B.C. 9.15.3.3)
HSS 4"x4"x1/4" ST. COL. C/W 6"x6"x 1/2" PL. TOP WELD TO BEAM & 6"x8" 1/2" BASE PL. C/W 2 - 1/2" DIA. 12" LONG 2" HOOK ANCHORS SET INTO CONC. FIELD WELD COL. TO BASE PL.

15A. ♦ STEEL BASEMENT COLUMN (SEE O.B.C. 9.15.3.3)
90mm(3-1/2") DIA x 4.78mm(.188) FIXED OR ADJUSTABLE STL. COL. W/ MAX ALLOWABLE LOAD OF 108.6kN (24,000LBS) W/ 150x150x9.5 (6"x6"x3/8") STL. TOP & BOTTOM PLATE ON 1070x1070x460 (42"x42"x18") CONC. FOOTING ON UNDISTURBED SOIL OR ENG. FILL CAPABLE OF SUSTAINING A PRESSURE OF 125 kPa. MIN. AND AS PER SOILS REPORT.

15B ♦ STEEL COLUMN
90mm(3-1/2") DIA x 4.78mm(.188) NON-ADJUSTABLE STL. COLUMN WITH 150x150x9.5 (6"x6"x3/8") STEEL TOP & BOTTOM PLATE. BASE PLATE 120x250x12.5 (4 1/2"x10"x1/2") WITH 2-12mm DIA. x 300mm LONG x50mm HOOK ANCHORS (2-1/2"x12"x2") FIELD WELD COLUMN TO BASE PLATE.

16. BEAM POCKET OR 200x200 (8"x8") POURED CONCRETE NIB WALLS. MINIMUM BEARING 90mm (3-1/2").

17. 19x64 (1"x3") CONTINUOUS WOOD STRAPPING BOTH SIDES OF STEEL BEAM.

18. ♦ GARAGE SLAB: 100mm (4") 32MPa (4640psi) CONC. SLAB WITH 5-8% AIR ENTRAINMENT ON OPT. 100 (4") COARSE GRANULAR FILL WITH COMPACTED SUB-BASE OR COMPACTED NATIVE FILL. SLOPE TO FRONT AT 1% MIN.

19. ♦ 15.87mm (5/8") GYPSUM BD. ON WALL AND CEILING BETWEEN HOUSE AND GARAGE, RSI 3.8 (R24) IN WALLS, RSI 5.5 (R31) IN CEILING. TAPE AND SEAL ALL JOINTS GAS TIGHT.

20. DOOR AND FRAME GASPROOFED. DOOR EQUIPPED WITH SELF CLOSING DEVICE AND WEATHERSTRIPPING.

21. PRECAST CONCRETE STEP OR WD. STEP WHERE NOT EXPOSED TO WEATHER. MAX. RISE 200mm (7-7/8"); MINIMUM TREAD 250mm (9-1/2").

22. CAPPED DRYER EXHAUST VENTED TO EXTERIOR.

23. ATTIC ACCESS HATCH 545x700 (22"x28") WITH WEATHERS TRIPPING. RSI 10.56 (R60) RIGID INSULATION BACKING.

24. ♦ FIREPLACE CHIMNEYS -OBC. 9.21.-
TOP OF FIREPLACE CHIMNEY SHALL BE 915mm (3'-0") ABOVE THE HIGHEST POINT AT WHICH IT COMES IN CONTACT WITH THE ROOF AND 610mm (2'-0") ABOVE THE ROOF SURFACE WITHIN A HORIZ. DISTANCE OF 3050mm (10'-0") FROM THE CHIMNEY.

25. LINEN CLOSET 4 SHELVES MIN. 350mm (14") DEEP.

26. MECHANICAL EXHAUST FAN, VENTED TO EXTERIOR, TO PROVIDE AT LEAST ONE AIR CHANGE PER HOUR.

27. ♦ STEEL BEARING PLATE FOR MASONRY WALLS
280x280x16 (11"x11"x5/8") STL. PLATE FOR STL BEAMS AND 280x280x12 (11"x11"x1/2") STL. PLATE FOR WOOD BEAMS BEARING ON CONC. BLK. PARTYWALL, ANCHORED W/ 2-19mm (3/4") x200mm (8") LONG GALV. ANCHORS WITHIN SOLID BLOCK COURSE. LEVEL WITH NON-SHRINK GROUT.
OR
SOLID WOOD BEARING FOR WOOD STUD WALLS
SOLID BEARING TO BE AT LEAST AS WIDE AS THE SUPPORTED MEMBER. SOLID WOOD BEARING COMPRISED OF BUILT-UP WOOD STUDS TO BE CONSTRUCTED IN ACCORDANCE WITH OBC. 9.17.4.2 (2).

28. U.L.C. RATED CLASS "B" VENT 610mm (2'-0") ABOVE THE POINT IN CONTACT WITH THE ROOF FOR SLOPES UP TO 9/12. REFER TO THE ONTARIO GAS UTILIZATION CODE.

29. 3-38x114 (3-2"x6") BUILT-UP-POST ON METAL BASE SHOE ANCHORED TO CONC. WITH 12.7 (1/2") DIA. BOLT, 610x610x300 (24"x24"x12") CONCRETE FOOTING.

30. STEP FOOTINGS: MIN. HORIZ. STEP = 600mm (23 5/8"). MAX. VERT. STEP = 600mm (23 5/8") FOR FIRM SOILS. 400mm (16") MAX. STEP FOR SAND AND GRAVEL.

31. ♦ MIN. 100mm (4") CONCRETE SLAB ON GRADE ON 100mm (4") COARSE GRANULAR FILL. REINFORCED W/ 6x6-W2.9xW2.9 MESH PLACED NEAR MID-DEPTH OF SLAB. CONC. STRENGTH 32 MPa.(4640 psi) WITH 5-8% AIR ENTRAINMENT ON COMPACTED SUB-GRADE.

32. DIRECT VENT FURNACE TERMINAL MIN. 900mm (36") FROM A GAS REGULATOR. MIN. 300mm (12") ABOVE FIN. GRADE, FROM ALL OPENINGS, EXHAUST & INTAKE VENTS. HRV INTAKE TO BE A MIN. OF 1830mm (6'-0") FROM ALL EXHAUST TERMINALS. REFER TO GAS UTILIZATION CODE.

33. DIRECT VENT GAS FIREPLACE. VENT TO BE A MINIMUM 300mm (12") FROM ANY OPENING AND ABOVE FIN. GRADE. REFER TO GAS UTILIZATION CODE.

34. ♦ SUBFLOOR, JOIST STRAPPING AND BRIDGING
-16mm (5/8") T & G SUBFLOOR ON WOOD FLOOR JOISTS. FOR CERAMIC TILE APPLICATION (* SEE OBC 9.30.6. *)
6mm (1/4") PANEL TYPE UNDERLAY UNDER RESILIENT & PARQUET FLOORING. (-* SEE OBC 9.23.9.4 *)
ALL JOISTS TO BE BRIDGED WITH 38x38 (2"x2") CROSS BRACING OR SOLID BLOCKING @ 2100mm (6'-11") O.C. MAX. ALL JOISTS TO BE STRAPPED WITH 19x64 (1"x3") @ 2100mm (6'-11") O.C. UNLESS A PANEL TYPE CEILING FINISH IS APPLIED.

35. ♦ EXPOSED BUILDING FACE -OBC. 9.10.14.11-
EXTERIOR WALLS TO HAVE A FIRE RESISTANCE RATING OF NOT LESS THAN 45 min. WHERE LIMITING DISTANCE IS LESS THAN 1.2M (3'-11"). WHERE THE LIMITING DISTANCE IS LESS THAN 600mm (1'-11") THE EXPOSING FACE SHALL BE CLAD IN NON-COMBUSTIBLE MATERIAL.

36. ♦ COLD CELLAR PORCH SLAB
6" 32MPa CONC. SLAB WITH 5-8% AIR ENTRAINMENT. WITH REINF. BARS AS NOTED. SLOPE SLAB MIN. 1.5% FROM DOOR.

37. THE FDTN. WALL SHALL NOT BE REDUCED TO LESS THAN 90mm (3-1/2") THICK TO A MAX. DEPTH OF 600mm (24") AND SHALL BE TIED TO THE FACING MATERIAL WITH METAL TIES SPACED 200mm (8") O.C. VERTICALLY AND 900mm (36") O.C. HORIZONTALLY. FILL SPACE BETWEEN WALL AND FACING SOLID WITH MORTAR.

38. ♦ CONVENTIONAL ROOF FRAMING
38x140 (2"x6") RAFTERS @ 400mm (16"O.C.), 38x184 (2"x8") RIDGE BOARD. 38x89 (2"x4") COLLAR TIES AT MIDSPANS. CEILING JOISTS TO BE 38x89 (2"x4") @ 400mm (16") O.C. FOR MAX. 2830mm (9'-3") SPAN & 38x140 (2"x6") @ 400 (16") O.C. FOR MAX. 4450mm (14'-7") SPAN. RAFTERS FOR BUILT-UP ROOF TO BE 38x89 (2"x4") @ 600mm (24") O.C. WITH A 38x89 (2"x4") CENTRE POST TO THE TRUSS BELOW, LATERALLY BRACED @ 1800mm (6'-0") O.C. VERTICALLY.

39. ♦ TWO STOREY VOLUME SPACES
FOR A MAXIMUM 5490 mm (18'-0") HEIGHT, PROVIDE 2-38x140 (2-2"x6") CONTINUOUS STUDS @ 300mm (12") O.C. FOR BRICK AND 400mm (16") O.C. FOR SIDING. PROVIDE SOLID WOOD BLOCKING BETWEEN STUDS @ 1220 mm (4'-0") O.C. VERT. FOR HORIZ. DISTANCES NOT EXCEEDING 2900 mm (9'-6"), PROVIDE 38x140 (2"x6") STUDS @ 400 mm (16") O.C. WITH A CONTINUOUS HEADER AT THE GROUND FLOOR CEILING LEVEL. TOENAILED AND GLUED TO TOP PLATES.

40. FLOOR ASSEMBLY
FLOORING LAYER AS PER OWNER
3/4" T & G PLYWD. GLUED AND SCREWED
FLOOR STRUCTURE - SEE STRUCTURAL
50 STC SOUND INSULATION
2 LAYERS OF 1/2" TYPE X GYPSUM BOARD CEILING ON METAL FURRING CHANELS @ 400MM O
10

Not examined for:
-electrical
-plumbing
-heating
-ventilation
-air conditioning

Floor assembly 40 shall comply with OBC - SB-3 floor assemblies with FRR=1.0 Hr. STC=50

4A wall assembly shall comply with OBC - SB-3 wall assemblies with FRR=1.0 Hr. STC=50

WINDOWS:

1) ♦ MINIMUM BEDROOM WINDOW -OBC. 9.7.1.3.-
AT LEAST ONE BEDROOM WINDOW ON A GIVEN FLOOR IS TO HAVE MIN. 0.35m2 UNOBSTRUCTED GLAZED OR OPENABLE AREA WITH MIN. CLEAR WIDTH OF 380 mm (1'-3").

2) WINDOW GUARDS -OBC. 9.7.1.6.-
A GUARD IS REQUIRED WHERE THE TOP OF THE WINDOW SILL IS LOCATED LESS THAN 480mm (1'-6") ABOVE FIN. FLOOR AND THE DISTANCE FROM THE FIN. FLOOR TO THE ADJACENT GRADE IS GREATER THAN 1800mm (5'-11")

WOOD LINTELS AND BUILT-UP WOOD BEAMS

L1	2/38 x 184 (2/2" x 8") SPR.#2
B1	3/38 x 184 (3/2" x 8") SPR.#2
B2	4/38 x 184 (4/2" x 8") SPR.#2
L3	2/38 x 235 (2/2" x 10") SPR.#2
B3	3/38 x 235 (3/2" x 10") SPR.#2
B4	4/38 x 235 (4/2" x 10") SPR.#2
L5	2/38 x 286 (2/2" x 12") SPR.#2
B5	3/38 x 286 (3/2" x 12") SPR.#2
B6	4/38 x 286 (4/2" x 12") SPR.#2

LOOSE STEEL LINTELS

L7	90 x 90 x 6.0L (3-1/2" x 3-1/2" x 1/4"L)
L8	100 x 90 x 8.0L (4" x 3-1/2" x 5/16"L)
L9	125 x 90 x 8.0L (5" x 3-1/2" x 5/16"L)
L10	150 x 100 x 10.0L (6"x 4" x 3/8"L)

A1 PACKAGE TO BE USED

THERMAL DESIGN FOR BUILDINGS OF RESIDENTIAL OCCUPANCY WITHIN THE SCOPE OF PART 9
MINIMUM INSULATION VALUES TO BE PROVIDED
Zone 1 - O.B.C. table 12.3.2.1 with non-electric heating

CEILING WITH ATTIC -	*R.S.I. 10.56 (R60)*
FLAT ROOF OR CATHEDRAL CEILING -	*R.S.I. 5.46 (R31)*
WALL ABOVE GRADE - *(other than foundation wall)*	*R.S.I. 3.87 (R22)*
FOUNDATION WALL -	*R.S.I. 3.52 (R20) C.I.*
EXPOSED FLOOR -	*R.S.I. 5.46 (R31)*

NOTE: MECHANICAL VENTILATION IS REQUIRED TO PROVIDE 0.3 AIR CHANGES PER HOUR AVERAGED OVER 24 HOURS. SEE MECHANICAL DRAWINGS.

LUMBER:
1) ALL LUMBER SHALL BE SPRUCE NO.2 GRADE, UNLESS NOTED OTHERWISE.
2) STUDS SHALL BE STUD GRADE SPRUCE, UNLESS NOTED OTHERWISE.
3) LUMBER EXPOSED TO THE EXTERIOR TO BE SPRUCE No.2 GRADE PRESSURE TREATED OR CEDAR, UNLESS NOTED OTHERWISE.
4) ALL LAMINATED VENEER LUMBER (L.V.L.) BEAMS, GIRDER TRUSSES, AND METAL HANGER CONNECTIONS SUPPORTING ROOF FRAMING TO BE DESIGNED & CERTIFIED BY TRUSS MANUFACTURER.
5) ♦ LVL BEAMS SHALL BE 1.9E WS MICRO-LAM LVL (Fb=2800psi.MIN.) OR EQUIVALENT. NAIL EACH PLY OF LVL WITH 89mm (3 1/2") LONG COMMON WIRE NAILS @ 300mm (12") O.C. STAGGERED IN 2 ROWS FOR 184, 240 & 300mm (7 1/4",9 1/2", 11 7/8") DEPTHS AND STAGGERED IN 3 ROWS FOR GREATER DEPTHS AND FOR 4 PLY MEMBERS ADD 1/2" (13mm) DIA. GALVANIZED BOLTS BOLTED AT MID-DEPTH OF BEAM @ 915mm (3'-0") O.C.
6) ♦ PROVIDE TOP MOUNT BEAM HANGERS TYPE "SCL" MANUFACTURED BY MGA CONNECTOR LTD. Tel. (905) 642-3175 OR EQUAL FOR ALL LVL BEAM TO BEAM CONNECTIONS UNLESS NOTED OTHERWISE.
7) JOIST HANGERS: PROVIDE METAL HANGERS FOR ALL JOISTS AND BUILT-UP WOOD MEMBERS INTERSECTING FLUSH BUILT-UP WOOD MEMBERS.
8) ♦ WOOD FRAMING NOT TREATED WITH A WOOD PRESERVATIVE, IN CONTACT WITH CONCRETE, SHALL BE SEPARATED FROM THE CONC. BY AT LEAST 2mil. POLYETHYLENE FILM, No.50 (45lbs.) ROLL ROOFING OR OTHER DAMPPROOFING MATERIAL, EXCEPT WHERE THE WOOD MEMBER IS AT LEAST 150mm (6") ABOVE THE GROUND.

STEEL:
1) ♦ STRUCTURAL STEEL SHALL CONFORM TO CAN/CSA-G40-21 GRADE 300W. HOLLOW STRUCTURAL SECTIONS SHALL CONFORM TO CAN/CSA-G40-21 GRADE 350W CLASS "H".
2) REINFORCING STEEL SHALL CONFORM TO CSA-G30-18M GRADE 400R.



BASEMENT FLOOR PLAN



GROUND FLOOR PLAN

Fire Door

FRR=1.0Hr. STC=50 plus OBC 9.11.1.4.

Where the limiting distance from the exposing building face (above finished ground level) to property line is less than 1.2m, minimum Fire Resistance Rating for that face to be considered 45 min. If LD is less than 0.6m then in addition to above condition the construction of cladding to be non-combustible.



Combined Space

SECOND FLOOR PLAN



ROOF PLAN

NOTE:
TYPICAL FOR ALL FLOORS:
- DOUBLE ALL JOISTS U/S PARTITION WALLS LOCATED PARALLEL TO JOISTS TYP.
- FLOOR SHALL BE 3/4" PLYWOOD, GLUED AND NAILED TO JOISTS TYP.
- PROVIDE SKEWED HANGERS H1,H2,H3,AND H4 AS REQUIRED BY SITE CONDITIONS.
- ALL JOISTS SHALL HAVE A MIN. BEARING OF 1 1/2" AT SUPPORTS TYP. U/N/O
- WOOD/PSL/LVL BEAMS SHALL HAVE A MIN. BEARING OF 3 1/2" AT SUPPORT TYP. U/N/O

CARLIFT GENERAL REVIEW: PROFESSIONAL ENGINEER TO VERIFY THE STRUCTURAL DESIGN OF THE REINFORCED CONCRETE SLAB OF GARAGE AND SUPPORTING STRUCTURE FOR ADEQUACY AND INTEGRITY PRIOR TO CONSTRUCTION AND VERIFY THE STRUCTURAL DESIGN OF CAR LIFT SUPPORTS, PROVIDE GENERAL REVIEW AND SUPERVISE CARLIFT INSTALLATION AND PROVIDE INSTRUCTION TO CONTRACTOR ON SAFE CONSTRUCTION PRACTICE IN COMPLIANCE WITH OBC REQUIREMENTS AND MANUFACTURER INSTRUCTION.



SECTION "A -A"



GARAGE SIDE (EAST) ELEVATION

Every floor level containing a bedroom in a suite shall be provided with at least one outside window that:
(a) is openable from the inside without the use of tools,
(b) provides an individual, unobstructed open portion having a minimum area of 0.35 m² with no dimension less than 380 mm, and
(c) maintains the required opening described in Clause (b) without the need for additional support.



GARAGE FRONT (SOUTH) ELEVATION

All openable windows shall be protected by guard or restrictor mechanism explained in OBC 9.8.8.1.(4) where the bottom edge of the openable portion of the window is located:
a) 900mm or less above the finished floor, or
b) 1800mm or more above the floor or ground on the other side of the window



GARAGE SIDE (WEST) ELEVATION



GARAGE REAR (NORTH) ELEVATION

LEGEND

	CLASS 'B' VENT	FD	FLOOR DRAIN
	EXHAUST VENT	HB	HOSE BIB
F.A.	FLAT ARCH	DJ	DOUBLE JOIST
M.C.	MEDICINE CABINET	TJ	TRIPLE JOIST
	CONC. BLOCK WALL	LVL OR TEMLAM	LAMINATED VENEER LUMBER
	DOUBLE VOLUME WALL SEE NOTE 39.	PL	POINT LOAD FROM ABOVE
		P.T.	PRESSURE TREATED LUMBER
		G.T.	GIRDER TRUSS BY ROOF TRUSS MANUF.

SB SOLID WOOD BEARING
SB2 - 2 MEMBER BUILT-UP STUD
SB3 - 3 MEMBER BUILT-UP STUD
SB4 - 4 MEMBER BUILT-UP STUD

SA SMOKE ALARM (REFER TO OBC 9.10.18)
PROVIDE 1 PER FLOOR, NEAR THE STAIRS CONNECTING THE FLOOR LEVEL. ALARMS TO BE CONNECTED TO AN ELECTRICAL CIRCUIT AND INTERCONNECTED TO ACTIVATE ALL ALARMS IF 1 SOUNDS.

CMD CARBON MONOXIDE DETECTOR (OBC 9.32.3.8)
* CHECK LOCAL BYLAWS FOR REQUIREMENTS *
A CARBON MONOXIDE DETECTOR CONFORMING TO CAN./CGA-6.19, SHALL BE INSTALLED ON OR NEAR THE CEILING IN EACH ROOM IN WHICH THERE IS INSTALLED A SOLID FUEL-BURNING APPLIANCE. CARBON MONOXIDE DETECTOR(S) SHALL BE WIRED SO THAT ITS ACTIVATION WILL ACTIVATE THE SMOKE ALARMS.

♦ SOIL GAS CONTROL (OBC 9.13.1.3 & 9.13.7.1)
PROVIDE CONSTRUCTION TO PREVENT LEAKAGE OF SOIL GAS INTO THE BUILDING IF REQUIRED.

COMPLIANCE PACKAGE

TORONTO Building
PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE
25 256572 BLD 00

ZONING	Makrigiorgos, Steven	08/Jul/2026
O.B.C.	Faghihi, Kamaledin	08/Jul/2026
FIRE SERVICES		
O.B.C. (S)		

Where the permit drawings and/or documents bear the seal of a professional engineer, no or limited review was carried out by Toronto Building to confirm that the matters to which the seal relates comply with the Ontario Building Code. As the seal denotes assumption of responsibility by the professional engineer, compliance with the Ontario Building Code was determined in whole or in part by reasonably relying solely on the seal of the professional engineer. Permit issuance does not absolve the owner or designers from ensuring compliance with the Ontario Building Code and applicable standards.

AREA CALCULATIONS	PROPOSED
GARAGE AREA	430.03 SF / 39.95 M2
SECOND FLOOR AREA	492.41 SF / 45.74 M2

No.	Revision	Date	By
10	FIRE ASSEMBLY ADDED	JAN/04/26	NS
9	WASHER & DRYER ADDED ; USE LABLED	DEC/7/25	NS
8	ISSUED FOR BUILDING PERMIT	NOV/10/25	NS
7	ISSUED FOR STRUCTURAL ENGINEERING DESIGN	OCT/22/25	NS
6	ISSUED FOR MECHANICAL DESIGN	OCT/22/25	NS
5	ISSUED FOR FLOOR AND ROOF ENGINEERING	OCT/22/25	NS
4	ISSUED FOR ZONING CERTIFICATE	OCT/22/25	NS
3	ADDED ANGULAR PLANE LINE	AUG/19/25	NS
2	ISSUED FOR ZONING REVIEW	JULY/21/25	NS
1	ISSUED FOR CLIENT REVIEW	OCT/08/24	NS

Drawn by: NICK SACCONE
Checked by:
Date plotted:

Contractor must verify all dimensions on the job and report any discrepancy to the architect before proceeding with the work. All drawings and specifications are instruments of service and the property of the architect which must be returned at the completion of the work. Drawings are NOT to be scaled.

TRADEMARKED BY DESIGN INC.
YOUR DREAM IS MY VISION...
103 GLEN LONG AVE
Toronto Ontario, M6B 2M4
Tel: (416) 829-3256 Fax: (416) 783-9042

Client: MR. NICOLA SACCONE, MRS. SANDRA SACCONE
Project Name: 173 WOBURN AVE, TORONTO, ONTARIO
Sheet Title: PLANS
Scale: 3/16"=1'-0"
Date: JANUARY 2023
Project No.: 23-173
File No.: 173-WOBURN-WD
Drawing No.: 1 / 2



EXISTING REAR (SOUTH) ELEVATION

Where the permit drawings and/or documents bear the seal of a professional engineer, no or limited review will be carried out by Toronto Building to confirm that the matters to which the seal relates comply with the Ontario Building Code. As the seal denotes assumption of responsibility by the professional engineer, compliance with the Ontario Building Code will be determined in whole or in part by reasonably relying solely on the seal of the professional engineer. Permit issuance does not absolve the owner or designers from ensuring compliance with the Ontario Building Code and applicable standards.

No.	Revision	Date	By
9	WASHER & DRYER ADDED ; USE LABLED	DEC/7/25	NS
8	ISSUED FOR BUILDING PERMIT	NOV/10/25	NS
7	ISSUED FOR STRUCTURAL ENGINEERING DESIGN	OCT/22/25	NS
6	ISSUED FOR MECHANICAL DESIGN	OCT/22/25	NS
5	ISSUED FOR FLOOR AND ROOF ENGINEERING	OCT/22/25	NS
4	ISSUED FOR ZONING CERTIFICATE	OCT/22/25	NS
3	ADDED ANGULAR PLANE LINE	AUG/19/25	NS
2	ISSUED FOR ZONING REVIEW	JULY/21/25	NS
1	ISSUED FOR CLIENT REVIEW	OCT/08/24	NS

TORONTO Building

PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE

25 256572 BLD 00

ZONING	Makrigiorgos, Steven	08/Jul/2026
O.B.C.		
FIRE SERVICES		
O.B.C. (S)		

Drawn by
NICK SACCONE

Checked by

Date plotted

LICENSED PROFESSIONAL ENGINEER
B. TORKAN
100142000
11/17/2025
PROVINCE OF ONTARIO

Contractor must verify all dimensions on the job and report any discrepancy to the architect before proceeding with the work. All drawings and specifications are instruments of service and the property of the architect which must be returned at the completion of the work. Drawings are NOT to be scaled.

TRADEMARKED BY DESIGN INC.

YOUR DREAM IS MY VISION...

103 GLEN LONG AVE
Toronto Ontario, M6B 2M4
Tel: (416) 829-3256 Fax: (416) 783-9042

Client: MR. NICOLA SACCONE
MRS. SANDRA SACCONE

Project Name: 173 WOBURN AVE
TORONTO, ONTARIO

Sheet Title: LIMITED DISTANCE AREAS

Scale: 3/16"=1'-0"

Date: JANUARY 2023

Project No.: 23-173

File No.: 173-WOBURN-WD

Drawing No. 2 / 2

Legend

ws	Web Stiffener
-ws	In Hanger Label Denotes Web Stiffener
	Wall
	TJ Rim Board 1.125 X 9.5
	MAX-CORE IB800 9.5
	2.0E Microllam LVL 1.75 X 9.5

Second Floor

LVL/LSL (Flush)

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
B2	2.0E Microllam LVL	1.75	9.5	2	2	4	6-0-0

I Joist (Flush)

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
J2	MAX-CORE IB800	3.5	9.5			20	20-0-0
J1	MAX-CORE IB800	3.5	9.5			4	6-0-0

Rim Board

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
R1	TJ Rim Board 1.125 X 9.5	1.125	9.5			7	12-0-0

Hanger

Label	Pcs	Description	Beam/Girder fasteners	Supported Member fasteners
Hg1	4	LT359	4 10dx1 1/2	2 10dx1 1/2

Blocking

Label	Description	Width	Depth	Qty	Pcs	Length
BLK1	IB800	3.5	9.5	LinFt	Varies	21-0-0

1. LEDGER DETAIL/CONNECTION BY OTHERS
2. ENGINEERED WOOD PRODUCTS ARE INTENDED FOR DRY PURPOSES ONLY. PREVENTION/PROTECTION BY OTHERS.
3. REFER TO MANUFACTURER INSTALLATION GUIDE FOR ALL CONSTRUCTION DETAILS.
4. JOIST LAYOUTS ARE FOR REFERENCE ONLY. REFER TO FINAL ENGINEERING SET OF PLANS.
5. ALL LOADS ARE UNFACTORED
6. REFER TO DETAIL "CS" WHEN TRANSFERRING POINT LOAD FROM ABOVE.
7. FLOOR LAYOUTS ARE TO BE APPROVED BY CUSTOMER PRIOR TO SHIPMENT
8. VERIFY ALL PLUMBING LOCATIONs PRIOR TO INSTALLATION. SPACING OF FLOOR JOIST TO BE ADJUSTED AND CONFIRMED BY FLOOR DESIGNER.
9. ALL DIMENSIONAL BEAMS, ROOF TRUSSES, SUPPORT STUDS' TALL WALLS, FOOTING PADS AND LATERAL BRACING DESIGNS ARE THE RESPONSABILITY OF PROFESSIONNAL ENGINEER.
10. CUSTOMER IS NOT GARANTEED RETURN/ REFUND OF PRODCUTS DUE TO ON-SITE REVISION.

Second Floor



Second Floor

Design Method	LSD (Canada)
Building Code	NBCC 2020 / 2024 OBC
Floor	
Loads	
Live	40
Dead	15
Deflection Joist	
LL Span L/	480
TL Span L/	240
Deflection Flush Girder	
LL Span L/	360
TL Span L/	240
Deflection Dropped Girder	
LL Span L/	360
TL Span L/	240
Deflection Header	
LL Span L/	360
TL Span L/	240
Decking	
Decking	SPF Plywood
Thickness	5/8"
Fastener	Nailed & Glued
Vibration	

Layout Name	173 Woburn Ave - Garage
Design Method	LSD
Description	
Created	octobre 14, 2025
Builder	Nobility Homes Ltd
Sales Rep	Kevin McCafferty
Designer	François Fortin
Shipping	173 Woburn Ave - Garage Toronto, ON
Project	202533706
Builder's Project	

RONA

RONA
220 ch du Tremblay
Boucherville, Quebec
Canada
J4B 8H7
514-599-5900

This placement plan is to be used as an installation guide only. It is meant to be used in conjunction with the manufacturers installation guide, the architectural and structural drawings, and not to replace them.

Legend

ws	Web Stiffener
-ws	In Hanger Label Denotes Web Stiffener
	Wall
	Wall Opening
	2.0E Microllam LVL 1.75 X 9.5 (Dropped)

Roof

LVL/LSL (Dropped)

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
H1	2.0E Microllam LVL	1.75	9.5	1	2	2	8-0-0

1. LEDGER DETAIL/CONNECTION BY OTHERS
2. ENGINEERED WOOD PRODUCTS ARE INTENDED FOR DRY PURPOSES ONLY. PREVENTION/PROTECTION BY OTHERS.
3. REFER TO MANUFACTURER INSTALLATION GUIDE FOR ALL CONSTRUCTION DETAILS.
4. JOIST LAYOUTS ARE FOR REFERENCE ONLY. REFER TO FINAL ENGINEERING SET OF PLANS.
5. ALL LOADS ARE UNFACTORED
6. REFER TO DETAIL "CS" WHEN TRANSFERRING POINT LOAD FROM ABOVE.
7. FLOOR LAYOUTS ARE TO BE APPROVED BY CUSTOMER PRIOR TO SHIPMENT
8. VERIFY ALL PLUMBING LOCATIONs PRIOR TO INSTALLATION. SPACING OF FLOOR JOIST TO BE ADJUSTED AND CONFIRMED BY FLOOR DESIGNER.
9. ALL DIMENSIONAL BEAMS, ROOF TRUSSES, SUPPORT STUDS' TALL WALLS, FOOTING PADS AND LATERAL BRACING DESIGNS ARE THE RESPONSABILITY OF PROFESSIONNAL ENGINEER.
10. CUSTOMER IS NOT GARANTEED RETURN/ REFUND OF PRODCUTS DUE TO ON-SITE REVISION.

TORONTO Building

PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE

25 256572 BLD 00

ZONING

O.B.C.

FIRE SERVICES

O.B.C. (S)



Roof

Design Method	LSD (Canada)
Building Code	NBCC 2020 / 2024 OBC

Roof

Loads

Live	0
Dead	18.4
Snow	20.9

Deflection Joist

LL Span L/	480
TL Span L/	240

Deflection Flush Girder

LL Span L/	360
TL Span L/	240

Deflection Dropped Girder

LL Span L/	360
TL Span L/	240

Deflection Header

LL Span L/	360
TL Span L/	240

Decking

Decking	SPF Plywood
Thickness	5/8"
Fastener	Nailed Only

Layout Name
173 Woburn Ave - Garage

Design Method
LSD

Description

Created
octobre 14, 2025

Builder
Nobility Homes Ltd

Sales Rep
Kevin McCafferty

Designer
François Fortin

Shipping
173 Woburn Ave - Garage
Toronto, ON

Project
202533706

Builder's Project

RONA
220 ch du Tremblay
Boucherville, Quebec
Canada
J4B 8H7
514-599-5900

RONA

TORONTO Building RECEIVED 24/Nov/2025

This placement plan is to be used as an installation guide only. It is meant to be used in conjunction with the manufacturers installation guide, the architectural and structural drawings, and not to replace them.



ROOF NOTES:
- OVERHANG FRAMED ON SITE BY OTHERS
- HATCHED AREAS FRAMED ON SITE BY OTHERS
- .5/12 AND 35/12 PITCHES
- 5 1/2" HEEL HEIGHT
- 1" AND 7" CLADDING ALLOWANCES PAST FRAME
- 2X6 BEARING WALLS
- ALL DIMENSIONS ARE TO OUTSIDE OF CLADDING
- DIMENSIONS READ AS FEET-INCHES-SIXTEENTHS
- ALL BEAMS/RAFTERS NOTED ARE BY OTHERS

TRUSS PEAK 30" ABOVE PLATE

All conventional roof framing to comply with O.B.C. 2024.
Roof rafters that meet or cross trusses below to be minimum 2x4 SPF #2 or better at maximum 24" o.c.
Rafters to be installed with minimum 2x4 SPF #2 or better vertical post to the truss below at each intersection (24" o.c. typical).
Vertical posts longer than 6' must be laterally braced at its midpoint.

WATFORD
ESTABLISHED 1972
Watford Roof Truss Ltd.
330 Front St.
Watford, Ontario
N0M 2S0
1-800-265-3470
Fax: 1-519-876-3200

CLIENT: Rona (Georgetown) #55250
BUILDER:
ADDRESS: 173 Woburn Avenue
CITY: Toronto, ON

JOB #: 16221A
MODEL:
DATE: 10/14/2025
DRAWN BY: jn

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC. 173 Woburn Avenue	DRWG NO.
16221A	A1	8	1	TRUSS DESC.	

Watford Roof Truss, Watford, Ont., Joe Noseworthy

ID:zCHiyj1778et9FNxp03hV7yTayq-hjq4?xZ8lTwbPoq31aKr9QGNKPei9uyTuk8NlNyTZBp



TORONTO Building
PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE
25 256572 BLD 00
ZONING
O.B.C.
FIRE SERVICES
O.B.C. (S)

TOTAL WEIGHT = 8 X 95 = 760 lb

[M][R]

LUMBER
N. L. G. A. RULES

CHORDS	SIZE		LUMBER	DESCR.
K - A	2x4	DRY	No.2	SPF
A - C	2x4	DRY	1650F 1.5E	SPF
C - E	2x4	DRY	1650F 1.5E	SPF
E - F	2x4	DRY	No.2	SPF
K - H	2x4	DRY	No.2	SPF
H - F	2x4	DRY	No.2	SPF
ALL WEBS	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TTW+h	MT20	4.0	12.0	3.00	1.50
B	TMWW-t	MT20	4.0	5.0	1.75	2.50
C	TTW-p	MT20	4.0	8.0	2.25	4.00
D	TMWW-t	MT20	4.0	5.0	1.75	2.50
E	TTW+h	MT20	4.0	12.0	3.00	1.50
F	TBM1-h	MT20	3.0	6.0	2.50	4.00
G	BMWW-t	MT20	5.0	12.0	2.50	4.75
H	BS-t	MII16	3.0	15.0		
I	BMWWW-t	MT20	4.0	8.0	1.75	4.00
J	BMWW-t	MT20	6.0	8.0	3.00	2.75
K	TBM1-h	MT20	3.0	6.0	0.50	5.00

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER
PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING

BEARINGS

JT	FACTORED GROSS REACTION VERT	HORZ	MAXIMUM FACTORED GROSS REACTION DOWN	HORZ	UPLIFT	INPUT BRG IN-SX	REQRD BRG IN-SX
K	1399	0	1399	0	0	5-8	5-8
F	1399	0	1399	0	0	5-8	5-8

UNFACTORED REACTIONS

JT	1ST LCASE COMBINED	MAX./MIN. COMPONENT REACTIONS SNOW	LIVE	PERM.LIVE	WIND	DEAD	SOIL
K	1012	538 / 0	0 / 0	0 / 0	0 / 0	474 / 0	0 / 0
F	1012	538 / 0	0 / 0	0 / 0	0 / 0	474 / 0	0 / 0

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S) K, F

BRACING
TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 2.70 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING
TOTAL LOAD CASES: (4)

C H O R D S

MEMB. FR-TO	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF) FROM	TO	MAX CSI (LC)	MAX. UNBRAC LENGTH
K- M	-1891 / 0	-88.7	-88.7	0.30 (4)	4.05
M- A	-1388 / 0	-88.7	-88.7	0.27 (4)	4.65
A- B	-3747 / 0	-88.7	-88.7	0.87 (1)	2.87
B- C	-4108 / 0	-88.7	-88.7	0.94 (1)	2.70
C- D	-4108 / 0	-88.7	-88.7	0.95 (1)	2.70
D- E	-3636 / 0	-88.7	-88.7	0.86 (1)	2.92
E- O	-1391 / 0	-88.7	-88.7	0.25 (1)	4.66
O- F	-1839 / 0	-88.7	-88.7	0.27 (1)	4.12
K- L	0 / 537	-20.0	-20.0	0.29 (4)	10.00
L- J	0 / 537	-20.0	-20.0	0.29 (4)	10.00
J- I	0 / 3741	-20.0	-20.0	0.92 (1)	10.00
I- H	0 / 3737	-20.0	-20.0	0.93 (1)	10.00
H- G	0 / 3737	-20.0	-20.0	0.93 (1)	10.00
G- N	0 / 532	-20.0	-20.0	0.27 (4)	10.00

W E B S

MEMB.	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
J- B	-787 / 0	0.11 (1)
B- I	0 / 379	0.08 (1)
I- C	-92 / 18	0.01 (1)
I- D	0 / 383	0.08 (1)
D- G	-801 / 0	0.12 (1)
A- J	0 / 3333	0.71 (1)
G- E	0 / 3234	0.69 (1)
L- M	0 / 523	0.00 (1)
N- O	0 / 463	0.00 (1)

DESIGN CRITERIA

SPECIFIED LOADS:

TOP CH.	LL	=	20.9	PSF
	DL	=	10.4	PSF
BOT CH.	LL	=	0.0	PSF
	DL	=	8.0	PSF
TOTAL LOAD		=	39.3	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2020

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2024, NBC-2023AE, MBC 2024, OBC 2024
- CSA 086-19
- TPIC 2019

(67 % OF 18.8 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 20.9 P.S.F. SPECIFIED ROOF LIVE LOAD

ALLOWABLE DEFL.(LL)= L/360 (0.86")
CALCULATED VERT. DEFL.(LL) = L/ 999 (0.23")
ALLOWABLE DEFL.(TL)= L/360 (0.86")
CALCULATED VERT. DEFL.(TL) = L/ 699 (0.44")

CSI: TC=0.95/1.00 (C-D:1) , BC=0.93/1.00 (G-I:1) , WB=0.71/1.00 (A-J:1) , SSI=0.63/1.00 (K-L:4)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00
FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY) (PSI) MAX	MIN	SHEAR (PLI) MAX	MIN	SECTION (PLI) MAX	MIN
MT20	650	371	1747	788	1987	1873

CONTINUED ON PAGE 2

G. XHAFA 100089397

TORONTO Building RECEIVED 24/Nov/2025

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC. 173 Woburn Avenue	DRWG NO.
16221A	A1	8	1	TRUSS DESC.	

Watford Roof Truss, Watford, Ont., Joe Noseworthy

ID:zCHiyj1778et9FNxp03hV7yTayq-9vOSCHamWn2S1yPFbHr4hepY3o_xuKCd7OtwHpyTZBo

LOADING
TOTAL LOAD CASES: (4)

CHORDS

MEMB. FR-TO	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF) FROM	TO	MAX CSI (LC)	MAX. UNBRAC LENGTH
N- F	0 / 532	-20.0	-20.0	0.27 (4)	10.00

WEBS

MEMB. FR-TO	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)

MII16 [illegible] 4.3 [illegible] 1.8 16

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

JSI GRIP= 0.89 (G) (INPUT = 0.90)
JSI METAL= 0.85 (H) (INPUT = 1.00)

TORONTO Building
PERMIT REVIEWED FOR COMPLIANCE WITH
THE ONTARIO BUILDING CODE

25 256572 BLD 00

ZONING		
O.B.C.		
FIRE SERVICES		

O.B.C. (S)

TORONTO Building RECEIVED 24/Nov/2025

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC. 173 Woburn Avenue	DRWG NO.
16221A	A2	2	1	TRUSS DESC.	

Watford Roof Truss, Watford, Ont., Joe Noseworthy

ID:zCHiyj1778et9FNxp03hV7yTayq-GPhNxjkwSnhc5yulrWa7jNrzM2e6RO6X6vX6FZyTZBb



TOTAL WEIGHT = 2 X 86 = 172 lb

[M][R]

LUMBER

N. L. G. A. RULES

CHORDS	SIZE		LUMBER	DESCR.
AC- A	2x4	DRY	No.2	SPF
A - G	2x4	DRY	No.2	SPF
G - M	2x4	DRY	No.2	SPF
M - N	2x4	DRY	No.2	SPF
AC- T	2x4	DRY	No.2	SPF
T - N	2x4	DRY	No.2	SPF
ALL WEBS	2x4	DRY	No.2	SPF
ALL GABLE WEBS	2x4	DRY	No.2	SPF

DRY: SEASONED LUMBER.

GABLE STUDS SPACED AT 2-0-0 OC.

PLATES (table is in inches)

JT	TYPE	PLATES	W	LEN	Y	X
A	TTW+m	MT20	3.0	6.0		
B, C, D, E, F, H, I, J, K, L						
B	TMW+w	MT20	2.0	6.0		
G	TTW+p	MT20	3.0	6.0		
M	TTW+m	MT20	3.0	6.0		
N	TBM1-h	MT20	3.0	6.0	2.00	2.75
O, P, Q, R, S, U, V, W, X, Y, Z, AA, AB						
O	BMW1+w	MT20	2.0	6.0		
T	BS-t	MT20	3.0	6.0		
AC	TBM1-h	MT20	3.0	6.0	0.75	3.50

DIMENSIONS, SUPPORTS AND LOADINGS SPECIFIED BY FABRICATOR TO BE VERIFIED BY BUILDING DESIGNER

PROVIDE ADEQUATE DRAINAGE TO PREVENT PONDING

BEARINGS

THIS TRUSS DESIGNED FOR CONTINUOUS BEARINGS.

THIS TRUSS REQUIRES RIGID SHEATHING ON EXPOSED FACE.

BEARING MATERIAL TO BE SPF NO.2 OR BETTER AT JOINT(S)

BRACING

TOP CHORD TO BE SHEATHED OR MAX. PURLIN SPACING = 6.25 FT.
MAX. UNBRACED BOTTOM CHORD LENGTH = 10.00 FT OR RIGID CEILING DIRECTLY APPLIED.

ALL PITCH BREAKS AND PERIMETER CORNER JOINTS MUST BE LATERALLY RESTRAINED.

LOADING

TOTAL LOAD CASES: (4)

CHORDS MEMB. FR-TO	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF) FROM	TO	MAX CSI (LC)	MAX. UNBRAC LENGTH	WEBS MEMB. FR-TO	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)
AC-AE	-30 / 0	-88.7	-88.7	0.00 (4)	6.25	V- G	-141 / 0	0.02 (1)
AE- A	-40 / 0	-88.7	-88.7	0.00 (1)	6.25	W- F	-201 / 0	0.03 (1)
A- B	-3 / 0	-88.7	-88.7	0.08 (1)	10.00	X- E	-171 / 0	0.03 (1)
B- C	-4 / 0	-88.7	-88.7	0.08 (1)	10.00	Y- D	-181 / 0	0.03 (1)
C- D	-3 / 0	-88.7	-88.7	0.06 (1)	10.00	Z- C	-166 / 0	0.02 (1)
D- E	-2 / 0	-88.7	-88.7	0.06 (1)	10.00	AA- B	-216 / 0	0.03 (1)
E- F	-1 / 0	-88.7	-88.7	0.07 (1)	10.00	AB- A	-62 / 0	0.01 (1)
F- G	-2 / 0	-88.7	-88.7	0.07 (1)	10.00	U- H	-201 / 0	0.03 (1)
G- H	-2 / 0	-88.7	-88.7	0.07 (1)	10.00	S- I	-171 / 0	0.03 (1)
H- I	-1 / 0	-88.7	-88.7	0.07 (1)	10.00	R- J	-181 / 0	0.03 (1)
I- J	-2 / 0	-88.7	-88.7	0.06 (1)	10.00	Q- K	-166 / 0	0.02 (1)
J- K	-3 / 0	-88.7	-88.7	0.06 (1)	10.00	P- L	-216 / 0	0.03 (1)
K- L	-4 / 0	-88.7	-88.7	0.08 (1)	10.00	O- M	-62 / 0	0.01 (1)
L- M	-3 / 0	-88.7	-88.7	0.08 (1)	10.00	AD-AE	-38 / 0	0.00 (1)
M-AG	-40 / 0	-88.7	-88.7	0.00 (1)	6.25	AF-AG	-38 / 0	0.00 (1)
AG- N	-30 / 0	-88.7	-88.7	0.00 (4)	6.25			
AC-AD	0 / 13	-20.0	-20.0	0.01 (1)	10.00			
AD-AB	0 / 13	-20.0	-20.0	0.02 (4)	10.00			
AB-AA	0 / 4	-20.0	-20.0	0.02 (4)	10.00			
AA- Z	0 / 3	-20.0	-20.0	0.02 (4)	10.00			
Z- Y	0 / 3	-20.0	-20.0	0.02 (4)	10.00			
Y- X	0 / 2	-20.0	-20.0	0.02 (4)	10.00			

DESIGN CRITERIA

SPECIFIED LOADS:

TOP	CH.	LL	=	20.9	PSF
		DL	=	10.4	PSF
BOT	CH.	LL	=	0.0	PSF
		DL	=	8.0	PSF
TOTAL	LOAD		=	39.3	PSF

SPACING = 24.0 IN. C/C

THIS TRUSS IS DESIGNED FOR RESIDENTIAL OR SMALL BUILDING REQUIREMENTS OF PART 9, NBCC 2020

THIS DESIGN COMPLIES WITH:
- PART 9 OF BCBC 2024, NBC-2023AE, MBC 2024, OBC 2024
- CSA 086-19
- TPIC 2019

(67 % OF 18.8 P.S.F. G.S.L. PLUS 8.4 P.S.F. RAIN LOAD) EQUALS 20.9 P.S.F. SPECIFIED ROOF LIVE LOAD

CSI: TC=0.08/1.00 (L-M:1) , BC=0.02/1.00 (O-P:4) , WB=0.03/1.00 (L-P:1) , SSI=0.12/1.00 (L-M:1)

DOL LUMBER=1.00 NAIL=1.00 LS BEND=1.10 COMP=1.10 SHEAR=1.10 TENS= 1.10

COMPANION LIVE LOAD FACTOR = 1.00
FLAT ROOF FACTOR = 0.75

TRUSS PLATE MANUFACTURER IS NOT RESPONSIBLE FOR QUALITY CONTROL IN THE TRUSS MANUFACTURING PLANT .

NAIL VALUES

PLATE	GRIP(DRY) (PSI) MAX	MIN	SHEAR (PLI) MAX	MIN	SECTION (PLI) MAX	MIN
MT20	650	371	1747	788	1987	1873

PLATE PLACEMENT TOL. = 0.250 inches

PLATE ROTATION TOL. = 5.0 Deg.

CONTINUED ON PAGE 2

G. XHAFA
100089397

JOB NAME	TRUSS NAME	QUANTITY	PLY	JOB DESC. 173 Woburn Avenue	DRWG NO.
16221A	A2	2	1	TRUSS DESC.	

ID:zCHiyj1778et9FNxp03hV7yTayq-lcEl83lYD4pTj6TxPE5NGbO85S_LArMgLZGfn?yTZBa

LOADING
TOTAL LOAD CASES: (4)

CHORDS

MEMB. FR-TO	MAX. FACTORED FORCE (LBS)	FACTORED VERT. LOAD LC1 (PLF) FROM	TO	MAX CSI (LC)	MAX. UNBRAC LENGTH
X- W	0 / 2	-20.0	-20.0	0.02 (4)	10.00
W- V	0 / 1	-20.0	-20.0	0.02 (4)	10.00
V- U	0 / 1	-20.0	-20.0	0.02 (4)	10.00
U- T	0 / 2	-20.0	-20.0	0.02 (4)	10.00
T- S	0 / 2	-20.0	-20.0	0.02 (4)	10.00
S- R	0 / 2	-20.0	-20.0	0.02 (4)	10.00
R- Q	0 / 3	-20.0	-20.0	0.02 (4)	10.00
Q- P	0 / 3	-20.0	-20.0	0.02 (4)	10.00
P- O	0 / 4	-20.0	-20.0	0.02 (4)	10.00
O-AF	0 / 13	-20.0	-20.0	0.02 (4)	10.00
AF- N	0 / 13	-20.0	-20.0	0.01 (1)	10.00

WEBS

MEMB. FR-TO	MAX. FACTORED FORCE (LBS)	MAX CSI (LC)

JSI GRIP= [illegible]
JSI METAL= 0.06 (B) (INPUT = 1.00)

81 Grandview Rd.
Ottawa, Ont. K2H 8B7
Tel: (613) 797-3812
Tel: 613 979 5801

AIMENG CANADA Inc.
Advancement in Management and Engineering

Email : gezim@fore-engineering.ca

July 31, 2024

To: Watford Roof Truss
Watford ON

SUBJECT: Use of scissor truss clips to allow for horizontal deflection for trusses of part 9 OBC

Truss Plate Institute of Canada in their design procedures allow for maximum horizontal deflection of 1” for any load combination case. To allow for this deflection one may use scissor truss clips with slotted holes. However for horizontal deflection up to 0.5”, if truss clip is not used, 3-3.5” toe nails may be used between truss and bearing (OBC P.9). This statement is valid for 3 years from the date shown on this letter.

Should you have any question, please feel free to contact us.

Yours truly,

LICENSED PROFESSIONAL ENGINEER
G. XHAFA
100089397
July 31, 2024
PROVINCE OF ONTARIO
this seal is for this structural component only
Refer to FT2024

Gezim Xhafa P.Eng.

81 Grandview Rd.
Ottawa, Ont. K2H 8B7
Tel: 613 797-3812
Tel: 613 979 5801

AIMENG CANADA Inc.
Advancement in Management and Engineering

Email: ash@fore-engineering.ca; gezim@fore-engineering.ca

March 6, 2024

Att: Jeff Balmain
Design manager
Watford Roof Truss
Watford ON

Addendum to letter of Substitution of one 1x4 lateral brace dated November 28, 2019

To whom it may concern,

For lateral brace of web in roof trusses, you may use 2x4 SPF#2 lumber. In regard to substitution one 2x4 SPF#2 lateral brace specified for web P.9 as per NBC/OBC in truss sealed by our company, It may be noted that you may use T brace as per TPIC appendix D. Lateral brace using a scab along web will be provided based on each individual case. This statement is valid for 3 years from the date shown on the letter.

Should you have any questions please feel free to contact us.

Yours truly,

LICENSED PROFESSIONAL ENGINEER
G. XHAFA
100089397
March 6, 2024
PROVINCE OF ONTARIO
this seal is for this structural component only
Refer to FT2024

Gezim Xhafa P.Eng.

TOE-NAIL CAPACITY DETAILS

LATERAL AND WITHDRAWAL RESISTANCE OF BEARING ANCHORAGE BY TOE NAILS

NAIL TYPE	Length (in)	Diameter (in)	LATERAL Resistance per nail (Lbs.)		WITHDRAWAL Resistance per nail (Lbs.)	
			SPF	D. FIR	SPF	D. FIR
COMMON WIRE	3.00	0.144	122	139	30	42
	3.25	0.144	127	144	32	45
	3.50	0.160	152	173	38	52
COMMON SPIRAL	3.00	0.122	96	108	26	36
	3.25	0.122	97	108	28	40
	3.50	0.152	142	161	36	50
3.25” Gun nail	3.25	0.120	94	105	28	39

Note: If using truss with D. Fir lumber and SPF bearing plate (or vice versa), use tabulated SPF values in table.

Nail type:	Common wire	Common spiral	Common wire	Common spiral	Gun Nail
Diameter (in.)	0.160	0.152	0.144	0.122	0.120
Length (in.)	3.50	3.50	3.00	3.00	3.25
LUMBER	**MAXIMUM NUMBER OF TOE-NAILS**				
2x4 SPF	2	2	3	3	3
2x6 SPF	4	4	4	4	4
2x4 D. FIR	2	2	2	2	2
2x6 D. FIR	3	3	3	4	4



Figure 1: Toe-Nailing Rafter / Ceiling Member to Girder Truss

TORONTO Building
PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE

25 256572 BLD 00

ZONING		
O.B.C.		
FIRE SERVICES		
O.B.C. (S)		

TOE-NAIL CAPACITY DETAILS

Figure 2: Toe-Nail Anchorage to Bearing Plate for Uplift





NOTES:

1. Rafter and ceiling members may be connected to top and bottom chords of girder truss by toe-nailing the members into the girder chords (see fig. 1), provided the factored vertical reactions of the supported members do not exceed the lateral resistance of the toe-nails. Appropriate mechanical connectors (angles or hangers) are required if factored vertical reactions exceed the toe-nail lateral resistance, or if the connection must resist horizontal withdrawal loads perpendicular to the plane of the girder truss.

2. Trusses, rafters or ceiling members may be anchored to the bearing plate with toe-nails (see fig. 2), provided that the factored uplift reactions due to **wind or earthquake loads** do not exceed the **withdrawal resistance of the toe-nails.** Mechanical anchors are required for reactions that exceed the toe-nail withdrawal capacity. Toe-nail anchorage to bearing plates is **NOT** permitted if uplift reactions are generated from gravity loads (snow, floor live, dead).

3. Tabulated toe-nail resistances on page 1 are for **one** toenail. Multiply unit values by the number of nails used in the connection. Maximum number of nails in a connection shall not exceed the tabulated limits shown on page 1 for a given lumber size / species.

4. Nail values are based on specific gravity of G = 0.42 (SPF) and G = 0.49 (D. Fir)

5. Toe-nails shall be driven at approximately 1/3 the nail length from the edge of the joist/truss chord and driven at an angle of 30° to the grain of the member.

6. Tabulated values are for standard load duration (K_D = 1.0). For wind / earthquake loads the tabulated lateral resistances may be multiplied by 1.15 (K_D =1.15). No increases are permitted for tabulated withdrawal resistances.

7. Lumber must be dry (< 19% moisture content) at the time of nail installation.

8. Nail values in this table comply with CSA O86-19, Clause 12.9.

9. This detail is a complementary detail for MiTek product lines and has not been prepared for a specific project. Decision on applicability of this detail to a specific project remains with the building designer of record.

PEO
Certificate No. 10889485
LICENSED PROFESSIONAL ENGINEER
2025-03-13
C. Cordogiannis
90553736
PROVINCE OF ONTARIO

TORONTO Building RECEIVED 24/Nov/2025

TORONTO Building
PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE
25 256572 BLD 00
ZONING
O.B.C.
FIRE SERVICES
O.B.C. (S)

STANDARD HIP END FRAMING

PLAN VIEW







Specified Load Rating:

Top chord Live:	51.0 PSF or less
Top chord Dead:	6.0 PSF or less
Bottom chord Live:	0.0 PSF
Bottom chord Dead:	7.3 PSF or less







CANTILEVER DETAIL "C"

SLOPE	MAX CANT.	WEDGE PLATE	WEDGE SIZE
3/12	17"	3 X 5	2 X 3
4/12	14"	3 X 5	2 X 3
5/12	12"	3 X 5	2 X 4
6/12	10"	3 X 5	2 X 4
7/12	9"	3 X 5	2 X 6
8/12	8.5"	3 X 5	2 X 6
9/12	8"	3 X 5	2 X 6
10/12	7.5"	3 X 5	2 X 6

J Trusses



PEO
Certificate No. 10889485

LICENSED PROFESSIONAL ENGINEER
2025-04-25
C. Cordogiannis
90553736
PROVINCE OF ONTARIO

NOTES:

1. This detail is valid only for projects complying with **PART 9 NBCC 2020** that do not require a wind analysis to be incorporated into the design of the trusses.
2. Overhang length shall not exceed 24 inches.
3. All lumber shall be 2x4 SPF (or D-Fir) DRY and of No. 2 grade or better.
4. All plates specified are MITEK MT20, pressed into both faces of each truss. Heel plates of all trusses shall conform to heel details 'A', 'B' or 'C'.
5. Diagonal hip rafter design shall conform to NBCC 2020 9.23.14.6 (minimum 2x6 SPF No.2)
6. For 6.0 ft. or less J-truss span, diagonal web on truss 'J" is optional. Girder design must reflect choice of partial jack ('J' with diagonal web) or open jack ('J' without diagonal web)
7. All connections shall be specified as per MITEK standard detail *'MSD2020-H: Toe-Nail Capacity Details'* (contact the truss supplier for truss end reactions at each connection point. Hangers may be required in high-snow regions).
8. **MSD2020-J** is a complementary detail for MiTek product lines and has not been prepared for a specific project. Decision on applicability of this detail to a specific project is the responsibility of the building designer of record.

TORONTO Building RECEIVED 24/Nov/2025

MiTek®

STANDARD DETAIL MSD2020-K

Issued: **MARCH 1, 2025**

Expiry: **APRIL 30, 2026**

TORONTO Building

PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE

STANDARD GABLE END DETAIL

25 256572 BLD 00







Notes:

1. This detail is only valid for projects complying with **Part 9, NBCC 2020** that do not require a wind analysis. to be incorporated into the design of the truss.
2. This detail is for vertical (gravity) load rating of the truss only. Truss must be continuously supported over the entire length of bottom chord.
3. Maximum web length not to exceed 12.0 ft. Spacing of gable stud webs in the truss not to exceed 24 inches cc.
4. Splice joints shall not be located in the first panel adjacent to the heel joint or peak joint.
5. Lateral restraint required at half-length of all webs over 6.0 ft. long. Alternatively install an L-Brace or scab brace as shown above. Scab braces shall be limited to 10 ft. long webs or less.
6. All plates are MITEK MT20 pressed into both faces of truss.
7. All lumber to be SPF (or D-Fir) DRY and of No.2 grade or better.
8. Additional building bracing is typically installed to brace the face of the end wall assembly. See BCSI Canada '*Building Designer Responsibilities for Gable End Frame Bracing*' for additional information on building bracing for gable-end assemblies.
9. This detail is a complementary detail for MiTek product lines and has not been prepared for a specific project. Decision on applicability of this detail to a specific project remains with the building designer of record.

PEO Certificate No. 10889485

LICENSED PROFESSIONAL ENGINEER
2025-03-13
C. Cordogiannis
90553736
PROVINCE OF ONTARIO

TORONTO Building **RECEIVED** 24/Nov/2025

STANDARD DETAIL MSD2020-L

Issued: **MARCH 1, 2025**
Expiry: **APRIL 30, 2026**

VALLEY SET DETAIL

VALLEY SET ROOF FRAMING PLAN





VALLEY TRUSS LUMBER:

Top Chord	**2x4**
Bottom Chord	**2x3 or 2x4**
Web	**2x3 or 2x4**

Splices (if required) shall be located at 1/4 point of a panel. Splice joints shall not be located in the first panel adjacent to the heel joint or peak joint. If beveling the bottom chord, splice plates shall be flush with top edge of bottom chord.



MITEK VTT
(Valley Truss Tie)



Install as per MiTek product installation instructions

NOTES:

1. Specified roof loads shall not exceed the maximum limits shown below:

Top chord:	Live =	**51.0**	PSF
Top Chord:	Dead =	**6.0**	PSF
Bottom Chord:	Live =	**0.0**	PSF
Bottom Chord:	Dead =	**7.3**	PSF

2. Valley truss design assumes full support by the truss system underneath. Spacing of all valley truses as well as the underlying trusses shall not exceed **24 in. c/c.**
3. Vertical web spacing in valley trusses not to exceed **48 in. c/c**. Web lengths not to exceed 12 ft.
4. All lumber to be DRY No. 2 grade or better, SPF or D-Fir.
5. Bottom chord may be beveled to match the slope of the intersecting roof. If beveling, a minimum 2x4 bottom chord is required, with a maximum bevel slope of 4/12 (spliced chord) or 8/12 (non-spliced chord). For bevel slopes exceeding the 2x4 limits, use a 2x6 bottom chord.
6. Truss plates are MITEK MT20 pressed into both faces of the truss and centered at each joint.
7. Use MiTek VTT Valley Truss Ties to attach each valley truss at the intersection point between valley chord and underlying truss chord. Install clips as per product installation instructions. Alternatively, toe- nail valley truss bottom chord at all intersection points with each underlying truss, using two 0.122”x3.25" nails per connection.
8. One continuous lateral brace is required at **½ length** of all valley webs that exceed 6.0 ft. in length.
9. This detail is only valid for residential projects complying with **PART 9 - NBCC2020,** that do not require a wind analysis to be incorporated into the design of the trusses.
10. This detail is a complementary detail for MiTek product lines and has not been prepared for a specific project. Decision on applicability of this detail to a specific project remains with the building designer of record.

PEO
Certificate No. 10889485

LICENSED PROFESSIONAL ENGINEER
2025-03-13
C. Cordogiannis
90553736
PROVINCE OF ONTARIO

MiTek®

STANDARD DETAIL MSD2020-I

Issued: **MARCH 1, 2025**

Expiry: **APRIL 30, 2026**

STANDARD PIGGYBACK TRUSS

TORONTO Building
PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE
25 256572 BLD 00
ZONING
O.B.C.
FIRE SERVICES
O.B.C.(S)

COMMON-SHAPED PIGGYBACK TRUSS



Specified Load Rating:		
Top chord live:	51.0	PSF
Top chord dead:	6.0	PSF
Bottom chord live:	0.0	PSF
Bottom chord dead:	7.3	PSF

Truss spacing not to exceed 24 inches cc

The design requirements and limits shown on this page are applicable to both common and mono-shaped piggybacks. Diagrams are for illustration purposes only.



MONO-SHAPED PIGGYBACK TRUSS

NOTES:

1. This detail is applicable only to projects complying with **PART 9 NBCC2020** that do not require a wind analysis to be incorporated into the truss design. Piggyback length not to exceed 24 ft.
2. All piggyback truss lumber to be SPF or D-Fir, and of grade No. 2 DRY (or better).
3. Piggyback top chord size shall be 2x4. Vertical webs and bottom chord sizes shall be 2x3 or 2x4.
4. Splice joints shall not be located in the first panel adjacent to the heel joint or peak joint. Splices shall be located at 1/4 length of any permissible panel.
5. Maximum web length not to exceed 12.0 ft. Maximum panel lengths not to exceed 48 inches.
6. One continuous lateral brace required at ½ length of all vertical members longer than 6.0 ft. Scab brace or L-brace substitutions are permitted. Scab braces shall be limited to 10 ft. long webs or less. Scab and L-braces shall cover 90% of web length and connected as per MITEK detail MSD2020-K.
7. Piggyback truss must be installed directly on top of each main truss.
8. All plates shall be MiTek MT20, centered at each joint and pressed into both faces of truss.
9. **DO NOT** cantilever mono-shaped piggyback truss over the end of main truss. Piggyback length must match the length of the flat chord of the main truss.
10. Purlin spacing shall be the lesser of 24" c/c or the main truss maximum unbraced top chord length (as shown on main truss engineering drawing).
11. Purlin design and overall roof system bracing shall be specified by the building designer.
12. Diagonal bracing required. See ***'BCSI CANADA -B2C: FIELD ASSEMBLY & OTHER SPECIAL CONDITIONS'***
13. This detail is a complementary detail for MiTek product lines and has not been prepared for a specific project. Decision on applicability of this detail to a specific project remains with the building designer of record.

PEO
Certificate No. 10889485

LICENSED PROFESSIONAL ENGINEER
2025-03-13
C. Cordogiannis
90553736
PROVINCE OF ONTARIO

TORONTO Building **RECEIVED** 24/Nov/2025

MiTek®

TORONTO Building
PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE
25 256572 BLD 00
ZONING
O.B.C.
FIRE SERVICES
O.B.C. (S)

ALTERNATIVE WEB BRACING SOLUTIONS

The scab brace detail shown on this page provides an alternative method of bracing compression webs of single ply trusses. Where the original design calls for web bracing, the scab-brace is an acceptable alternative provided that the factored axial force in the web member does not exceed the tabulated values shown below. This detail applies to web lengths of 5.0 ft. to 10.0 ft. only. For intermediate web lengths do not interpolate, use the tabulated value of the longer length. (ex. For a 6.25 ft. web, use the tabulated values for a 6.5 ft. web)

Maximum factored web force, Lbs (1PLY Truss)

WEB LENGTH (Ft.)	2x3	2x4	2x5	2x6	2x8+
5.00	3209	4493	5777	7061	9308
5.50	2749	3848	4947	6047	7971
6.00	2345	3283	4221	5158	6800
6.50	1998	2797	3596	4395	5794
7.00	1704	2386	3067	3749	4942
7.50	1457	2039	2622	3205	4225
8.00	1250	1749	2249	2749	3624
8.50	1075	1505	1935	2365	3117
9.00	929	1300	1672	2044	2694
9.50	807	1129	1452	1775	2339
10.00	704	985	1267	1548	2041

SCAB BRACE DETAIL
1-PLY TRUSS



NOTES:

1. This detail **SHALL NOT** be used to repair damaged webs.
2. Scab and web sizes must be equal (i.e., use a 2x6 scab on a 2x6 web, etc.).
3. Scab & web lumber must be DRY (≤ 19% moisture content) at time of installation.
4. Scab must cover minimum 90% of the entire length of web.
5. For 2x12 webs use 2x10 nail pattern, but with 5 rows of nails instead of 4.
6. This detail is for webs loaded axially only (not for axial/bending members).
7. Web and scab lumber shall be SPF No. 2 (or better)
8. Tabulated resistances are for standard load duration only (K_D=1.0) and DRY service conditions (K_S =1.0). Do not use detail for WET service applications.
9. This detail shall be used only in conjunction with sealed MiTek truss drawings.
10. This detail is a complementary detail for MiTek product lines and has not been prepared for a specific project. Decision on applicability of this detail to a specific project remains with the building designer of record.

SCAB CONNECTION: 1-PLY TRUSS



+ 0.122" dia. x 3.0" nail driven from front face
o 0.122" dia. x 3.0" nail driven from back face

Note: Connect scabs to truss along their entire length.

PEO
Certificate No. 10889485
LICENSED PROFESSIONAL ENGINEER
2025-03-13
C. Cordogiannis
90553736
PROVINCE OF ONTARIO

TORONTO Building **RECEIVED** 24/Nov/2025

MiTek®

STANDARD DETAIL **MSD2020-P**

Issued: **MARCH 1, 2025**

APRIL 30, 2026

TORONTO Building
PERMIT REVIEWED FOR COMPLIANCE WITH THE ONTARIO BUILDING CODE
25 256572 BLD 00
ZONING
O.B.C.
FIRE SERVICES
O.B.C. (S)

ALTERNATIVE WEB BRACING SOLUTIONS

The scab brace detail shown on this page provides an alternative method of bracing compression webs of 2-PLY trusses. Where the original design calls for web bracing, the scab-brace is an acceptable alternative provided that the maximum factored axial force in the web member does not exceed the tabulated values shown below. This detail applies to web lengths of 5.0 Ft. to 10.0 Ft. only. For intermediate web lengths, do not interpolate, use the tabulated value of the longer length. (ex. For a 6.25 ft. web, use the tabulated values for a 6.5 ft. web)

Maximum factored web force, Lbs (2PLY Truss)

WEB LENGTH (Ft.)	2x3	2x4	2x5	2x6	2x8+
5.00	6419	8987	11554	14122	18615
5.50	5497	7696	9895	12094	15942
6.00	4689	6565	8441	10317	13599
6.50	3996	5594	7193	8791	11588
7.00	3408	4771	6134	7498	9883
7.50	2913	4079	5244	6410	8449
8.00	2499	3499	4498	5498	7248
8.50	2150	3010	3870	4730	6235
9.00	1858	2601	3344	4087	5388
9.50	1613	2259	2904	3549	4678
10.00	1408	1971	2534	3097	4082

SCAB BRACE DETAIL
2-PLY TRUSS



NOTES:

1. This detail **SHALL NOT** be used to repair damaged webs.
2. Scab sizes must be equal to web size (i.e. use a 2x6 scab on a 2x6 web, etc.).
3. Scabs &web lumber must be DRY (≤ 19% moisture content) at time of installation.
4. Scabs must cover 90% of the entire length of web and installed on both faces.
5. This detail shall NOT apply to vertical webs used for girder load transfer.
6. Web & scab lumber to be SPF No. 2 (or better) grade.
7. This detail is for webs loaded axially only (not for axial/bending members).
8. Ensure scabs will not interfere with incoming trusses, prior to using this detail.
9. Tabulated resistances are for standard load duration only (K_D=1.0) and DRY service conditions (K_S =1.0). Do not use detail for WET service applications.
10. This detail shall be used only in conjunction with sealed MiTek truss drawings.
11. This detail is a complementary detail for MiTek product lines and has not been prepared for a specific project. Decision on applicability of this detail to a specific project remains with the building designer of record.

SCAB CONNECTION: 2-PLY TRUSS



+ MITEK MIFLK006 Screw @ 8 in. cc

Note: Connect scabs to truss along their entire length.

PEO
Certificate No. 10889485

LICENSED PROFESSIONAL ENGINEER
2025-03-13
C. Cordogiannis
90553736
PROVINCE OF ONTARIO

TORONTO Building RECEIVED 24/Nov/2025

AimEng

AIMENG CANADA INC.

Advancement in Management and Engineering

81 Grandview Rd.
Ottawa, Ontario
K2H 8B7
613-797-3812

AIMENG Engineering notes (FT2024)

DESIGN INFORMATION

All truss designs are based on the information provided by the client. The sealing engineer disclaims any responsibility for damages incurred by faulty or incorrect information, specification and/or designs provided to engineer by the client. Aimeng Canada inc. is only responsible for the structural integrity of the sealed trusses for the conditions shown on this drawing. The structural integrity of the building and the verification of the dimensions and the design loads indicated on the drawing is the responsibility of the building designer or project engineer.

CODE

This truss has been designed in accordance with national building code of Canada, CSA & TPIC engineering guidelines.

LUMBER

1. Lumber used must be of the same grade and size as indicated on the drawing.
2. Lumber used, must not be treated by any fireproofing, corrosive or chemical materials.
3. Lumber must be free of splits and cracks.
4. Moisture content of lumber at time of manufacture should be <u>less than 15% for seasoned lumber</u> and <u>more than 15% for unseasoned lumber.</u>

CONNECTOR PLATES

1. Plates shall be located on both faces of the truss with teeth fully embedded and shall be symmetrical about the center of the joint, unless shown otherwise with a joint detail.
2. Plates shall not be installed over knotholes, knots or distorted grain.
3. Bottom chord flush plates must be used at bearing locations, where post (post must be greater or equal to bearing width) is perpendicular to bottom chord, unless stated otherwise by engineer or actual bearing is larger than 1.5 times the required bearing size.
4. Calculations are based upon the plate tolerance shown in drawings.

CALCULATION

1. Where lateral bracing is shown to the side of a member, it must be attached to that member with 2-3" nails in 2x4 brace and 3-3" nails in 2x6 brace. Bracing is to be positioned to provide equal segments. In the absence of continuous lateral bracing, 2x4 T-brace must be nailed flat to edge of member as per TPIC Appendix D. T-brace and must extend 90% of member length.
2. Compression chords (top or bottom) are assumed to be continuously braced by sheathing unless otherwise specified.
3. Roof trusses in P.9. Where bottom chords are in tension and not fully braced laterally by a properly applied rigid ceiling, they must be braced at a min. 10'-0" o.c.
4. Use the truss in a dry environment unless specifically indicated on the truss drawing.

FABRICATION HANDLING AND INSTALLATION

1. Prior to fabrication, the fabricator shall review this drawing to verify that the information is in conformance with his plans.
2. Members must be cut to ensure tight fit wood-to-wood contact.
3. Drilling or cutting of webs is not permitted.
4. Handling and erection of trusses must be carried out by a qualified person in accordance with procedures outlined by the TPIC.
5. Prevent truss rotation and lateral displacement at all support locations.
6. Use care during banding or bundling, delivery and installation to avoid damage to trusses.
7. The trusses are to be installed straight and plumb to bearing plate, using min. 3-(3-1/2") toenails with minimum 1-1/2" penetration in bearing plate.
8. Connection and anchorage of the truss to bearing plate and design of all supporting structural elements are the responsibility of the building designer and project engineer.
9. Temporary and permanent bracings are for holding trusses in a straight and plumb position. All bracings required for resisting lateral forces shall be designed by project engineer and installed by others.
10. Truss must be installed in dry non corrosive environment unless noted otherwise on engineering drawing
11. All plies of any girder are to be connected to corresponding plies by connection patterns outlined by the TPIC design procedures.